

## Clayton Environmental Consultants

A Marsh & McLennan Company

---

Groundwater Monitoring Investigation  
at  
Stoody Company  
City of Industry, California

Clayton Project No. 21171.00  
June 22, 1989

1941 27 10 10

1941 27 10 10

## CONTENTS

|  | <u>Page</u> |
|--|-------------|
| <b><u>EXECUTIVE SUMMARY</u></b>  |             |
| 1.0 <b><u>INTRODUCTION</u></b> .....   | 1           |
| 1.1 <b><u>BACKGROUND</u></b> .....   | 1           |
| 1.2 <b><u>OBJECTIVE</u></b> .....  | 1           |
| 1.3 <b><u>SCOPE OF WORK</u></b> .....  | 2           |
| 2.0 <b><u>GROUNDWATER INVESTIGATION</u></b> .....                                    | 3           |
| 2.1 <b><u>GROUNDWATER MONITORING WELL INSTALLATION</u></b> .....                     | 3           |
| 2.2 <b><u>GROUNDWATER MONITORING WELL DEVELOPMENT AND SAMPLING</u></b> .....         | 4           |
| 2.3 <b><u>SURVEYING OF MONITORING WELL WELLHEADS</u></b> .....                       | 5           |
| 2.4 <b><u>DEVELOPMENT OF FIRST-GROUNDWATER CONTOURS AND FLOW DIRECTION</u></b> ..... | 5           |
| 2.5 <b><u>INSTALLATION OF UPGRADIENT MONITORING WELL</u></b> .....                   | 6           |
| 3.0 <b><u>LABORATORY ANALYTICAL RESULTS</u></b> .....                                | 7           |
| 3.1 <b><u>SOIL SAMPLE ANALYTICAL RESULTS</u></b> .....                               | 7           |
| 3.2 <b><u>GROUNDWATER SAMPLE ANALYTICAL RESULTS</u></b> .....                        | 7           |
| 4.0 <b><u>DISCUSSION</u></b> .....   | 8           |
| 5.0 <b><u>CONCLUSIONS</u></b> .....  | 9           |
| 6.0 <b><u>RECOMMENDATIONS</u></b> .....  | 10          |
| 7.0 <b><u>REFERENCES CITED</u></b> .....   | 11          |

### **Figures**

- 1 GENERAL SITE LOCATION AND TOPOGRAPHY
- 2 APPROXIMATE LOCATIONS OF SOIL BOREHOLES AND MONITORING WELLS
- 3 GROUNDWATER TABLE CONTOURS AND FLOW DIRECTION

### **Tables**

- 1 GROUNDWATER MONITORING WELL DATA
- 2 COMPOUNDS DETECTED IN SOIL SAMPLES
- 3 COMPOUNDS DETECTED IN GROUNDWATER SAMPLES

**CONTENTS (CONTINUED)**

**Appendices**

- A CRWQCB APPROVAL**
- B BOREHOLE LOGS**
- C WELL COMPLETION DIAGRAMS**
- D WATER SAMPLING FIELD SURVEY FORMS**
- E WELL SURVEY DIAGRAMS**
- F GROUNDWATER FLOW DIRECTION CALCULATION**
- G LABORATORY ANALYTICAL RESULTS AND CHAIN-OF-CUSTODY FORMS**

## **EXECUTIVE SUMMARY**

Clayton Environmental Consultants, Inc. was retained by the Stody Company to develop a general housekeeping plan, and to develop and implement an initial subsurface soil investigation at their facility located at 16425 Gale Avenue in the City of Industry, California.

The housekeeping plan and initial subsurface investigation were requested by the California Regional Water Quality Control Board (CRWQCB), as a result of their March 1988 inspection of the Stody Company facility.

Information gathered during the initial subsurface investigation begun in July 1988 led the CRWQCB to request the preparation and implementation of a groundwater monitoring workplan at the facility.

The objective of the implemented groundwater monitoring investigation was to assess the condition of groundwater located beneath the facility. General activities included in the investigation were groundwater monitoring well installation (including subsurface soil sample collection and analysis), groundwater sample collection and analysis, and report preparation.

Laboratory analysis of soil samples collected during monitoring well installation indicated relatively low concentrations of a small number of chemical compounds. Based on these relatively low concentrations, and the low concentrations of compounds detected in soil samples collected during the initial subsurface soil investigation, it appears that soil remediation is not necessary.

Laboratory analysis of groundwater samples showed that various chemical compounds were present in the groundwater. However, it appears that these are attributable to offsite sources.



Groundwater Monitoring Investigation  
at  
Stoody Company  
City of Industry, California

Clayton Project No. 21171.00  
June 22, 1989

**Clayton Environmental Consultants, Inc.**

P.O. Box 788 • 5736 Corporate Avenue • Cypress, California 90630 • (714) 229-4806

**1.0 INTRODUCTION**

This document presents the report of the activities associated with the groundwater monitoring investigation conducted at the Stoody Company facility located at 16425 Gale Avenue in the City of Industry, California (Figure 1).

**1.1 BACKGROUND**

On March 16, 1988, the Stoody Company facility was inspected by California Regional Water Quality Control Board (CRWQCB) staff member Mr. Dainis Kleinbergs. As a result of that inspection, Stoody was directed to develop a general housekeeping plan and to conduct an initial subsurface soil investigation at their City of Industry facility.

In June of 1988, Clayton Environmental Consultants, Inc. was retained by Stoody to develop the general housekeeping plan and to develop and implement the initial subsurface soil investigation work plan. On July 19, 1988 Clayton obtained approval of the proposed housekeeping plan and initial subsurface investigation workplan from Mr. Roy Sakaida of the CRWQCB. The initial subsurface investigation was implemented in July 1988. Clayton's final report of that investigation was presented to the CRWQCB on October 19, 1988 (Clayton Project Number 49537-73). Included with the soil investigation report was Stoody's proposed groundwater monitoring work plan, as required by the CRWQCB.

Clayton began implementation of the groundwater monitoring work plan in January 1989 after receiving approval from both the CRWQCB (Appendix A) and Stoody Company.

**1.2 OBJECTIVE**

The objective of the groundwater monitoring investigation was to assess the condition of groundwater located beneath the facility.

### 1.3 SCOPE OF WORK

Activities included in the groundwater monitoring investigation were as follows:

- Continue drilling of previously drilled Soil Borehole SB-5. Collect a soil sample immediately above groundwater.
- Drill one vertical borehole adjacent to the chemical waste barrel storage area. Collect soil samples immediately below the ground surface and immediately above the groundwater.
- Drill one vertical soil borehole at the northeast corner of the main facility building. Collect soil samples immediately below ground surface (bgs) and immediately above groundwater. Collect a soil sample from the saturated groundwater zone and submit this sample for grain size analysis.
- Seal, preserve, and ship soil samples to a California state-certified laboratory for analysis, using standard chain-of-custody procedures.
- Utilize grain size analysis and other data to design groundwater monitoring wells.
- Drill the three boreholes to 21 feet below groundwater surface. Install groundwater monitoring wells (MW-1, MW-2, MW-3).
- Survey the wellheads of the three wells installed. (A professional surveyor used an established benchmark to measure the elevation of each well head with respect to mean sea level).
- Calculate site groundwater flow direction and gradient using the well survey information.
- Develop and purge the three monitoring wells after installation. Collect groundwater samples after development, and submit them for laboratory analysis.
- Install an upgradient monitoring well (MW-4) in line with the nearest downgradient well. Collect soil samples during the drilling of the borehole drilled for the installation of Monitoring Well MW-4 and submit them for laboratory analysis.
- Survey the wellhead of Monitoring Well MW-4.
- Develop and purge Monitoring Well MW-4 after installation. Collect groundwater samples after well development, and submit them for laboratory analysis.
- Evaluate the field data and laboratory analytical results.
- Prepare a final report.





## **2.0 GROUNDWATER INVESTIGATION**

### **2.1 GROUNDWATER MONITORING WELL INSTALLATION**

On January 23, 1989, Monitoring Wells MW-1, MW-2, and MW-3 were installed onsite in the locations shown on Figure 2. Monitoring well permits were obtained from the Los Angeles County Department of Health Services.

The monitoring wells were designed after (1) review of the California Site Mitigation Decision Tree Manual (May 1986), (2) "Selection and Installation of Well Screens and Gravel Packs" (undated), and (3) review of field observations from initial drilling and soil sampling. Based on a grain-size analysis and field observation of fine-grained soil materials, Clayton decided to use a 0.01-inch well casing slot size. We believe that the next available larger slot size (0.02-inch) would allow formation materials to rather readily enter the well bore, and the next available smaller size (0.006-inch) might clog with formation materials or hinder water flow into the wellbore. The wells were installed with a Number 2 Monterey-type sand. This sand pack was partially developed, as explained below, to minimize the potential for bridging and to better "pack" the sand pack into place.

Soil Boreholes SB-6 and SB-7 were drilling, sampled, and converted to Monitoring Wells MW-1 and MW-2, respectively. Monitoring Well MW-3 was installed in the previously-drilled soil borehole, SB-5.

A Mobile B-61 drill rig was used to advance continuous-flight, hollow-stem, 11-inch outside diameter (O.D.) augers in the boreholes. Augers were steam-cleaned between boreholes to minimize the potential for cross contamination.

Soil samples were collected and retained for analysis at 1 and 25 feet bgs in Boreholes SB-6 and SB-7, and at 25 feet bgs in the previously drilled SB-5. Soil samples were collected at 1, 5, and 10 feet bgs in SB-5 during the initial subsurface soil investigation. Samples were also collected at 5, 10, 15, 20, and 30 feet bgs in Boreholes SB-6 and SB-7 and at 15, 20, and 30 feet in Borehole SB-5. However, these samples were used for soil description and field analysis and were not submitted for laboratory analysis as no field indications of contamination were observed. The samples were collected using a 2-1/2-inch inside diameter (I.D.) split-barrel sampler lined with two 6-inch by 2-1/2-inch brass sample tubes. The split-barrel sampler was cleaned with tap water and TSP (trisodium phosphate) and rinsed with tap water between sampling intervals. The boreholes were logged by a Clayton geologist working under the supervision of a California Registered Geologist. Borehole logs are provided in Appendix B.

Two soil samples were collected at each depth. The first brass sample tube collected at each depth was sealed on each end with aluminum foil, plastic end caps, and electrical tape. It was then labeled, inserted in a self-sealing plastic bag, and placed on "blue-ice" in a portable ice chest. The samples were transported to West Coast Analytical Services, Inc. in Santa Fe Springs, California for analysis following standard chain-of-custody procedures.

Soil from the second sample collected at each depth was subjected to field headspace analysis. This was done by half-filling an 8-ounce glass jar with soil taken from the second sample tube and capping the jar with a Teflon<sup>TM</sup>-lined lid. These samples were allowed to volatilize in direct sunlight for a minimum of 30 minutes. At the end of the volatilization period, the sensor end of a Photovac<sup>TM</sup> photoionization detector (PID) was inserted into a predrilled, tape-covered hole in the jar lid. The level of volatile organic compounds (VOCs) in the jar

headspace, as measured by the PID, was recorded on the borehole logs (Appendix B). The PID meter was also used to monitor worker breathing zone and borehole soil cutting VOC concentrations.

After groundwater was encountered in each borehole, the augers were removed from the borehole and a wooden plug installed in the lead auger. The augers were advanced to 21 feet below the encountered groundwater level in each borehole. After total depth was reached in a borehole, the augers were filled with deionized water up to the groundwater level and the wooden plug knocked out of the lead auger. This procedure was followed in each borehole to minimize the heaving of soils into the augers by equalizing hydrostatic pressure.

After removal of the plug, the well casing was lowered into the annular space of the augers. The casing consisted of 4-inch inside diameter (I.D.) Schedule 40 threaded PVC. Thirty feet of 0.01-inch machine slotted well screen with a threaded PVC end cap made up the lower portion of each well. This was topped by blank casing which extended upward to the ground surface. The blank casing was topped by locking, water-tight well caps.

The well filter pack (Number 2 Monterey-type sand) was hand-poured into the annular space of the augers, between the augers and the well casing. The filter pack extended from 1 foot below the bottom of the casing to approximately 3 feet above the top of the screened interval of the casing. The wells were partially developed with a surge block to settle the filter pack. Additional filter pack was added after settling to maintain the desired level of the filter pack.

After filter pack installation, 1/4-inch diameter bentonite pellets were hand-placed, as a well seal, on top of the filter pack. The pellets were hydrated with deionized water, maintaining a ratio of approximately 1 gallon of water per 6-inch layer of pellets. The pellets were allowed to hydrate for approximately 30 minutes. After that time, a cement-bentonite grout was placed on top of the well seal. Locking, flush-mounted, heavy-duty well head boxes were imbedded in the cement grout to protect the wellheads. The well completion diagrams are provided in Appendix C.

## **2.2 GROUNDWATER MONITORING WELL DEVELOPMENT AND SAMPLING**

### **2.2.1 Well Development**

The monitoring wells (MW-1, MW-2, and MW-3) were developed 7 days after installation on January 30, 1989. Well development was performed with a steel bailer and surge block attached to a truck-mounted mast/pulley system.

The wells were bailed initially with the steel bailer to remove sediment present in the bottom of the wells. The surge block was then used to surge the screened interval of the wells. The block was raised and lowered in 3-foot intervals within the screened portion of the wells. This was done to draw sediment into the well bore. After surging was completed, the wells were bailed again with the stainless steel bailer to remove the sediment brought into the wells by surging.

After the bailing and surging cycle was completed, five casing volumes of water were removed from each well, using the bailer. In addition, the amount of water added to the wells during installation was also removed by bailing. Water quality parameters (pH, temperature, and electrical conductivity) were measured during bailing. Development was discontinued on each well after the measured parameters were within 10 percent of those

of the previous casing volume, indicating parameter stabilization, and the water drawn from the wells appeared relatively free of suspended sediment.

#### **2.2.2 Well Sampling**

The wells (MW-1, MW-2, and MW-3) were sampled 10 days after installation on February 2, 1989. A minimum of three casing volumes of water was removed from each well. The water was removed through the use of hand-held PVC bailers. Water quality parameters (pH, temperature, and electrical conductivity) were measured after each casing volume was removed (Appendix D). Bailing was discontinued after the parameters stabilized to within 10 percent of the values obtained from the previous casing volume.

Hand-held Teflon™ bailers, attached to nylon line, were used to collect the groundwater samples. The bailers were cleaned with tap water and TSP between sampling events. The washing was followed by a double rinse with tap water. New sections of nylon line were used at each well. The samples were collected using containers and preservatives deemed appropriate by the sampling and preservation guidelines of the U.S. EPA (EPA 40 CFR 136). The sample containers were labeled, wrapped in shock-absorbing foam sheeting, and placed on ice in a portable cooler. The samples were transported to Clayton's state-certified laboratory in Pleasanton, California for analysis.

Groundwater removed from the wells during sampling was placed in Class 17-H, 55-gallon drums appropriate for water collection. The drums were labeled and placed in an appropriate location onsite for disposal by Stoodly Company.

### **2.3 SURVEYING OF MONITORING WELL WELLHEADS**

The wellheads of the monitoring wells were transit-surveyed by a registered professional civil engineer after installation was completed.

The elevation of the top of the casing of each well was surveyed, relative to mean sea level, from an established local benchmark. Horizontal distances and vertical elevations are accurate to within 0.01 feet. The well survey diagram showing the wellhead locations and California coordinates is provided in Appendix E. The well head coordinates are also listed in Table 1.

### **2.4 DEVELOPMENT OF FIRST-GROUNDWATER CONTOURS AND FLOW DIRECTION**

The elevation of the top of the casing of each well, with respect to mean sea level, was provided from the well survey. Elevations were surveyed from City of Industry Benchmark G5A. Depth to groundwater was measured in each well, using a Slope Indicator Co. water level indicator. Well casing elevations and depth to groundwater measurements were used to calculate water table elevations in each well. These are listed in Table 1. The three measured water levels and surveyed horizontal distances between the wells were used to approximate a triangular area upon the groundwater table, which was assumed to have a planar orientation in the subsurface. This allowed for the use of a standard 3-point graphic and geometric solution (geologic 3-point problem) to calculate groundwater contour elevations and flow direction (Appendix F). Groundwater elevation contours from 323 to 327 feet above mean sea level (with a 1-foot contour interval) are shown on Figure 3. The calculations performed using the water level data indicate that groundwater flow direction is to the west-northwest (Figure 3).

## 2.5 INSTALLATION OF UPGRADIENT MONITORING WELL

Following the assessment of groundwater flow direction, an upgradient monitoring well (Monitoring Well MW-4) was installed on March 6, 1989. Monitoring Well MW-4 was placed in its location at the direction of the CRWQCB. Its location is upgradient of the previously installed wells as indicated by Clayton's assessment of groundwater flow direction.

A Mobil B-61 drill rig was used to advance continuous-flight, hollow-stem, 11-inch O.D. augers. Soil samples were collected at 1 and 25 feet bgs. Sampling procedures and headspace analysis procedures used in the previous drilling episodes were followed. The borehole log is provided in Appendix B.

After groundwater was encountered, the augers were removed from the borehole and a wooden plug was inserted into the lead auger. The augers were placed in the borehole and drilling was continued to 21 feet below the encountered groundwater level. The augers were then filled up to the groundwater level with deionized water and the plug was knocked out of the augers. As before, this was done to minimize the heaving of formational material into the augers.

The groundwater monitoring well was installed using the procedures and design used for the first three wells that were installed. The well completion diagram is included in Appendix C.

The monitoring well was developed on March 10, 1989 and sampled on March 28, 1989. Development and sampling procedures outlined previously were employed during these field operations. The groundwater samples were shipped, following standard chain-of-custody procedures, to Clayton's Pleasanton, California laboratory for analysis. Soil samples were shipped to West Coast Analytical Services, Inc. in Santa Fe Springs, California.

The groundwater removed during development and sampling was placed in Class 17-H, 55-gallon drums. These were labeled and placed in an appropriate location onsite for disposal by Stoddy Company.

The wellhead of Monitoring Well MW-4 was also surveyed by a professional surveyor. Its elevation and location in relation to California coordinates are shown in Table 1 and on the diagram included in Appendix E.



### 3.0 LABORATORY ANALYTICAL RESULTS

Laboratory analyses were provided by Clayton's laboratory, located in Pleasanton, California and by West Coast Analytical Services, Inc., located in Santa Fe Springs, California. Both laboratories are certified by the California Department of Health Services.

The soil samples submitted for analysis were analyzed in accordance with Environmental Protection Agency (EPA) Methods 8240 (for volatile organics) and 418.1 (for total petroleum hydrocarbons).

The groundwater samples were analyzed using EPA Method 624 (for purgeable organics).

Laboratory analytical results are summarized in Tables 2 and 3. Laboratory analytical reports, along with the appropriate chain-of-custody forms, are provided in Appendix G.

### 3.1 SOIL SAMPLE ANALYTICAL RESULTS

As stated, the soil samples were analyzed using EPA Methods 8240 and 418.1, which test for volatile organic compounds and total petroleum hydrocarbons, respectively.

Soil samples collected at 1 and 25 feet bgs in Boreholes SB-5, SB-6, and SB-7 (converted to MW-1, MW-2, and MW-3, respectively) were submitted for analysis. In addition, soil samples collected at 5, 10, 15, 20, and 25 feet bgs in Borehole MW-4 were submitted for analysis.

As indicated by the laboratory analytical reports, analysis by EPA Method 8240 showed that carbon disulfide was detected in the sample collected at 25 feet bgs in Borehole SB-6 at a concentration of 7 micrograms per kilogram (ug/kg).

Using EPA Method 8240, acetone was detected in soil samples collected from Borehole MW-4, at concentrations ranging from 30 to 48 ug/kg. Also, methylene chloride was detected at a concentration of 52 ug/kg in the sample collected at 20 feet bgs in Borehole MW-4.

Soil samples from boreholes SB-5, SB-6, SB-7 and MW-4 were analyzed for total petroleum hydrocarbons (TPH) using EPA Method 418.1. Laboratory analytical reports of analysis by EPA Method 418.1 indicate that TPH were not detected at a detection limit of 10 mg/kg. Laboratory analytical results of the soil samples are summarized in Table 2.

### 3.2 GROUNDWATER SAMPLE ANALYTICAL RESULTS

The groundwater samples collected from monitoring wells MW-1, MW-2, MW-3, and MW-4 were analyzed for purgeable organic compounds using EPA Method 624.

As indicated by the laboratory analytical reports, a variety of compounds were detected in the groundwater samples. These compounds and their concentration ranges are as follows: (1) 1,1-dichloroethene at 11 to 61 micrograms per liter (ug/L); (2) trichloroethene at 25 to 130 ug/L; (3) tetrachloroethene at 55 to 190 ug/L; (4) toluene at 3 ug/L; (5) freon 113 at 3 to 10 ug/L; (6) benzene at 31 ug/L; and (7) chlorobenzene at 39 ug/L. Not all compounds listed above were detected in samples from each well. Table 3 lists the various compounds detected in each sample and their respective concentrations.





#### 4.0 DISCUSSION

As stated in Sections 3.1 and 3.2, various chemical compounds were detected in some of the soil and groundwater samples that were submitted for analysis. In the following section we will recap our discussion of these compounds as given in Sections 3.1 and 3.2. Additionally, we will discuss the significance of the absence (in the soil samples) of compounds detected in the groundwater. The concentrations of the detected compounds were compared to drinking water action levels (State Action Levels or SALs) developed by the California Department of Health Services (DHS; January 1987), and to guidance cleanup levels developed by the California Regional Water Quality Control Board, Central Valley Region (CRWQCB, November 1985, revised September 1987), and designated levels to protect groundwater in a solid as developed by the CRWQCB. The guidance cleanup level values were taken from examples of designated levels of chemical compounds for a hypothetical "average" site in a solid (soil) to protect groundwater.

Of the soil samples collected in Boreholes SB-5, SB-6, and SB-7, only one contained detectable concentrations of a chemical compound. Carbon disulfide, at a concentration of 7 ug/kg, was found in the sample collected at 25 feet bgs in SB-6 (converted to MW-2). No SAL, guidance cleanup level, or designated level was listed for this compound.

Relatively minor concentrations of acetone were detected in the MW-4 soil samples. As indicated in Table 2, this compound was detected in the samples collected at 5, 10, 15, 20, and 25 feet bgs at concentrations of 30, 34, 37, 45, and 48 ug/kg, respectively. No SAL, guidance cleanup level, or designated level was listed for acetone.

The soil sample collected at 20 feet bgs in MW-4 was found to contain methylene chloride at a concentration of 52 ug/kg. This is slightly above the 40 ppb SAL for methylene chloride.

Of the various compounds detected in groundwater samples collected from Monitoring Well MW-1, three exceeded their SALs; 1,1-dichloroethene at 31 ug/kg (6 ppb SAL), trichloroethene at 130 ug/kg (5 ppb SAL), and tetrachloroethene at 190 ug/L (100 ppb SAL). However, all three compounds were also detected in the upgradient well (MW-4). These compounds were not detected in the soil samples collected from either the MW-1 location or from the MW-4 location. These data indicate an offsite source for the compounds detected in the groundwater.

The groundwater samples collected from Monitoring Well MW-3 contained two compounds that exceeded their SALs; trichloroethene at 25 ug/L (5 ug/L SAL) and tetrachloroethene at 64 ug/L (4 ug/L SAL). However, as before, these compounds were also detected in the upgradient MW-4 groundwater samples and were not detected in the soil samples collected from the MW-3 location or the MW-4 location. Once again, an offsite source for these compounds is indicated.

Analytical results of the groundwater samples collected from Monitoring Well MW-2 report that seven compounds were detected (Table 3). Of these, five exceeded their SALs. However, three of these compounds were also detected in the upgradient well (MW-4) groundwater samples and were not detected in soil samples collected onsite. Additionally, the other two compounds detected in the MW-2 groundwater sample were not detected in soil samples collected onsite. This again indicates an offsite source for these compounds.



## 5.0 **CONCLUSIONS**

Eight soil boreholes were drilled onsite to depths ranging from 10 to 46 feet bgs. Five of these were drilled during the initial subsurface soil investigation and the remaining three were drilled during the following groundwater investigation. Groundwater monitoring wells were installed in four of these boreholes.

Soil/groundwater samples were collected from each borehole/well and subjected to laboratory analysis using one or more of the following EPA Methods as appropriate: 8240, 418.1, and 624.

Groundwater depth in the wells varied from 24.11 to 26.32 feet bgs from top of casing, across the site. Based on surveyed wellhead elevations and measured depths to water, groundwater flow direction was calculated to be to the west-northwest. Groundwater contour elevations across the site range from 323 to 327 feet above mean sea level.

Laboratory analyses of soil samples collected in the boreholes drilled for monitoring well installation showed relatively minor concentrations of a few purgeable organic compounds including carbon disulfide, methylene chloride and acetone.

Laboratory analyses of groundwater samples collected from the downgradient monitoring wells (MW-1, MW-2, and MW-3) report some compounds at concentrations above their respective SALs. However, the majority of these compounds are also present in samples collected from Monitoring Well MW-4, (the upgradient monitoring well). Additionally, no compounds detected in the monitoring wells were detected in the soil samples collected onsite. These data indicate an offsite source (or sources) for these compounds.



## **6.0 RECOMMENDATIONS**

Our stated conclusions lead Clayton to make the following recommendations:

- The subsurface investigation report should be submitted to the CRWQCB for their review and approval.
- Chemical compound concentrations detected in soil do not exceed CRWQCB guidance cleanup levels, where established. Therefore, no further work is thought to be necessary concerning soil.
- Analysis of groundwater samples indicates that groundwater beneath the site has been impacted by chemical compounds. It appears that these chemicals have originated from offsite sources. This should be assessed through additional investigation by the following tasks:
  - (1) Resample Monitoring Wells MW-1, MW-2, MW-3, and MW-4 and analyze the collected groundwater samples.
  - (2) Investigate environmental regulatory agency records concerning hazardous material incidents in surrounding upgradient areas in an attempt to identify possible offsite sources for compounds detected in the groundwater samples.

7

7.0 **REFERENCES CITED**

California Department of Health Services, Toxic Substances Control Division, Alternative Technology and Policy Development Section, The California Site Mitigation Decision Tree Manual, May 1986.


California Regional Water Quality Control Board, Central Valley Region, November 21, 1985, Guidance Document (Draft), Waste Classification and Cleanup Level Determination by Jon B. Marshack, Environmental Specialist, Environmental Support Section.

National Water Well Association, Selection and Installation of Well Screens and Gravel Packs, undated.


State of California, Drinking Water Action Levels Recommended by the Department of Health Services: State of California Department of Health Services, January 1987.

United States Department of the Interior, Geological Survey; 1964, topographic map of the La Habra Quadrangle, 1966, Topographic Map of the Baldwin Park Quadrangle, California, Scale 1:24,000, Photorevised 1981.


This report prepared by:

  
Kenneth J. Vernon  
Geologist

This report approved by:

  
David H. Randell, R.G.  
Registered Geologist No. 3977  
Supervisor, Environmental Engineering  
Southern California Operations

June 22, 1989



The Stoddy  
Company



Basemap from USGS, 1966, Baldwin Park Quadrangle, 7 1/2 Minute series (topographic), photorevised 1981

**Clayton Environmental Consultants, Inc.**

GENERAL SITE LOCATION AND TOPOGRAPHY

Stoddy Company

Project No. 21771.00

6/89

Figure



1





- ⊕ Soil borehole location
- ⊕ Soil borehole/monitoring well location

SCALE: 1" = 150'



Clayton Environmental Consultants, Inc.

APPROXIMATE LOCATIONS OF  
SOIL BOREHOLES AND MONITORING WELLS


Stoody Company

Project No. 21171.00

Figure

2

6/89



0 165 feet

Scale: 1" = 165'

| Clayton Environmental Consultants, Inc.          |                      | Figure |
|--|----------------------|--------|
| GROUNDWATER TABLE CONTOURS<br>AND FLOW DIRECTION |                      | 3      |
| Stoody Company                                   | Project No. 21171.00 | 6/89   |

**TABLE 1**  
**GROUNDWATER MONITORING WELL DATA**

| Monitoring Well                       | MW-1         | MW-2         | MW-3         | MW-4         |
|---------------------------------------|--------------|--------------|--------------|--------------|
| California Coordinates, Northerly     | 4 115 307.68 | 4 115 400.79 | 4 115 618.57 | 4 115 298.41 |
| California Coordinates, Easterly      | 4 304 954.04 | 4 305 006.99 | 4 304 433.62 | 4 305 083.28 |
| Elevation of top of well casing (MSL) | 352.18       | 351.12       | 349.34       | 353.55       |
| Total depth of well                   | 45 feet      | 45 feet      | 45 feet      | 44.92 feet   |
| Date of measurement                   | 2/2/89       | 2/2/89       | 2/2/89       | 3/28/89      |
| Depth to water from top of casing     | 25.14 feet   | 24.11 feet   | 26.32 feet   | 26.30        |
| Elevation of water (MSL)              | 327.04 feet  | 327.01 feet  | 323.02       | 327.25       |
| Date of measurment                    | 6/16/89      | 6/16/89      | 6/16/89      | 6/16/89      |
| Depth to water from top of casing     | 27.15        | 25.22        | 27.40        | 26.95        |
| Elevation of water (MSL)              | 325.03       | 325.90       | 321.94       | 326.94       |

**TABLE 2**  
**COMPOUNDS DETECTED IN SOIL SAMPLES**

| Sample I.D. | Detected Compound and Concentration<br>Compound<br>Concentration<br>(ug/kg or ppb) | Guidance Cleanup<br>(mg/kg or ppm) | Designated Level<br>to protect<br>groundwater in a solid<br>(ug/kg or ppb) |
|-------------|--|------------------------------------|--|
| SB-6, 25'   | Carbon Disulfide   | 7                                  | *  |
| MW-4, 5'    | Acetone  | 30                                 | *  |
| MW-4, 10'   | Acetone  | 34                                 | *  |
| MW-4, 15'   | Acetone  | 37                                 | *  |
| MW-4, 20'   | Acetone  | 45                                 | *  |
| MW-4, 20'   | Methylene Chloride   | 52                                 | 190  |
| MW-4, 25'   | Acetone  | 48                                 | *  |

\* No level listed

ug/kg - microgram per kilogram generally equivalent to parts-per-billion (ppb)  
mg/kg - milligram per kilogram generally equivalent to parts-per-million (ppm)

**TABLE 3**  
**COMPOUNDS DETECTED IN GROUNDWATER SAMPLES**

| Sample I.D. | <u>Detected Compound and Concentration</u> |                      | State Action Level (ppb) |
|-------------|--|----------------------|--------------------------|
|             | Compound                                   | Concentration (ug/l) |                          |
| MW-1        | 1,1-dichloroethene                         | 31                   | 6                        |
|             | Trichloroethene                            | 130                  | 5                        |
|             | Tetrachloroethene                          | 190                  | 4                        |
|             | Toluene                                    | 3                    | 100                      |
|             | Freon 113                                  | 10                   | 18,000                   |
| MW-2        | 1,1-dichloroethene                         | 61                   | 6                        |
|             | Trichloroethene                            | 130                  | 5                        |
|             | Benzene                                    | 31                   | .7                       |
|             | Tetrachloroethene                          | 160                  | 4                        |
|             | Toluene                                    | 39                   | 100                      |
|             | Chlorobenzene                              | 39                   | 30                       |
|             | Freon 113                                  | 8                    | 18,000                   |
| MW-3        | Trichloroethene                            | 25                   | 5                        |
|             | Tetrachloroethene                          | 64                   | 4                        |
| MW-4        | 1,1-dichloroethene                         | 11                   | 6                        |
|             | Trichloroethene                            | 44                   | 5                        |
|             | Tetrachloroethene                          | 55                   | 4                        |
|             | Freon 113                                  | 3                    | 18,000                   |

ug/l - microgram per liter  
 ppb - parts per billion

## Appendix A

**APPENDIX A**  
**CRWQCB APPROVAL**

CALIFORNIA REGIONAL WATER QUALITY CONTROL BOARD—  
LOS ANGELES REGION107 SOUTH BROADWAY, SUITE 4027  
LOS ANGELES, CALIFORNIA 90012-4596  
(213) 620-4460

RECEIVED

JAN 15 1989



January 11, 1989

Mr. Hal Kahlen  
STOODY/STOODY DELORO SATELLITE, INC.  
16425 Gale Avenue  
City of Industry, CA 91745

WORK PLAN APPROVAL (FILE NO. AB105.263)

Board staff is in receipt of your supplementary work plan provisions, as prepared by Clayton Environmental Consultants. Review of the work plan with provisions indicates that Board minimum and site specific requirements have been met. Therefore, approval is granted. Please contact Board staff at least one week prior to implementation of the work plan. Four copies of the assessment report must be submitted to Board staff. If there are any further questions, you may contact Dainis Kleinbergs at (213) 620-5982.

ROY R. SAKAIDA  
Senior Water Resource  
Control Engineer

RRS:dk

cc: David Randell, Clayton Environmental Consultants  
Ken Vernon, Clayton Environmental Consultants



## Appendix B

## **APPENDIX B**

### **BOREHOLE LOGS**

PROJECT NO. 21171.00 DATE 3/6/89

BORING NO.

CLIENT Stooddy Company

MW-4

LOCATION 16425 Gale Avenue, Industry, California

Sheet 1

LOGGED BY K. Vernon

DRILLER H-F

of 2

LOG OF  
EXPLORATORY BORINGField Location of Boring: South of barrel storage  
area near east property line.Drilling method: Continuous-flight, hollow-stem  
augers.

Ground Elev.: Datum:

Casing Installation Data: 44' of 4-inch dia.  
schedule 40 PVC; 14.92 of blank and 30 feet of  
0.01" screen Hole Dia. 11"

| Drilling<br>Rate<br>FT/MIN | PID<br>OVA | D<br>E<br>P<br>T<br>H | S<br>A<br>M<br>P<br>L<br>E | Soil<br>Group<br>Symbol<br>(uscs) | Litho-<br>Graphic<br>Symbol | Water Level  | 26 feet |  |  |  |
|----------------------------|------------|-----------------------|----------------------------|-----------------------------------|-----------------------------|--|---------|--|--|--|
|                            |            |                       |                            |                                   |                             | Time   |         |  |  |  |
|                            |            |                       |                            |                                   |                             | Date   | 3/6/89  |  |  |  |
|                            |            |                       |                            |                                   |                             | DESCRIPTION  |         |  |  |  |
|                            |            | 0-3"                  | AU                         | SM                                |                             | Asphalt  |         |  |  |  |
|                            | ND         | 1'                    | SS                         |                                   |                             | SILTY SAND: Brown (5/3), 10-15% silt, fine-<br>grained, poorly graded, moderately firm, mod-<br>erate plasticity, dominantly quartz, damp,<br>odorless.  |         |  |  |  |
|                            |            |                       |                            |                                   |                             |  |         |  |  |  |
|                            | ND         | 5'                    | SS                         | ML                                |                             | SILT: Brown (5/3), very firm, moderate plasti-<br>city, damp, odorless.  |         |  |  |  |
|                            |            |                       |                            |                                   |                             |  |         |  |  |  |
|                            |            |                       |                            |                                   |                             |  |         |  |  |  |
|                            | ND         | 10'                   | SS                         | SW                                |                             | GRAVELY SAND: Light brown (6/4), 15-20% pebble<br>gravel (dominantly quartz and feldspar), medium<br>to coarse grained, moderately well graded, sub-<br>angular, moderately loose, dominantly quartz,<br>damp, odorless. |         |  |  |  |
|                            |            |                       |                            |                                   |                             |  |         |  |  |  |
|                            | ND         | 15'                   | SS                         | SW                                |                             | GRAVELY SAND: Light brown (6/4), 15-20% pebble<br>gravel, coarse to medium grained, moderately<br>well graded, subangular to subrounded, loose,<br>dominantly quartz, damp, odorless.                                    |         |  |  |  |
|                            |            |                       |                            |                                   |                             |  |         |  |  |  |
|                            | ND         | 20'                   | SS                         | SW                                |                             | GRAVELY SAND: Light brown (6/4), 20-25% pebble<br>gravel, medium to fine-grained, moderately<br>well graded, subrounded, loose, dominantly<br>quartz, moist, odorless.   |         |  |  |  |
|                            |            |                       |                            |                                   |                             |  |         |  |  |  |
|                            | ND         | 25'                   | SS                         | SP                                |                             | GRAVELY SAND: Light brown (6/4), 15-20% pebble<br>gravel, fine-grained, poorly graded, subrounded,<br>loose, dominantly quartz, wet odorless.  |         |  |  |  |
|                            |            |                       |                            |                                   |                             |  |         |  |  |  |
|                            |            | 26-46*                | AU                         | SP                                |                             | GRAVELY SAND: Brown (6/4), 10-15% pebble gravel,<br>fine- to medium-grained (dominantly fine), poorly<br>graded, subrounded, loose, dominantly quartz,<br>wet, odorless.   |         |  |  |  |
|                            |            |                       |                            |                                   |                             |  |         |  |  |  |
|                            |            |                       |                            |                                   |                             |  |         |  |  |  |

[illegible]

CLAYTON ENVIRONMENTAL  
CONSULTANTS, INC.

PROJECT NO. 21171.00 DATE 7/21/88 & 1/23/89  
 CLIENT Stoody Company  
 LOCATION 16425 Gale Avenue, Industry, California  
 LOGGED BY K. Vernon DRILLER H-F

BORING NO.  
 SB-5  
 Sheet 1  
 of 2

LOG OF  
EXPLORATORY BORING

Field Location of Boring: Northwest of main building  
 south of drain in general storage area.

Ground Elev.: \_\_\_\_\_ Datum: \_\_\_\_\_

Drilling method: Continuous-flight, hollow-stem  
 augers.

Casing Installation Data: See below.

Hole Dia. 11"

| Drilling<br>Rate<br>FT/MIN | PID<br>OVA | D<br>E<br>P<br>T<br>H | S<br>A<br>M<br>P<br>L<br>E | Soil<br>Group<br>Symbol<br>(uscs) | Litho-<br>Graphic<br>Symbol | Water Level | No water encountered on 7/21/89 | Time | Water encountered at 26 feet on | Date | 1/23/89 | DESCRIPTION   |
|----------------------------|------------|-----------------------|----------------------------|-----------------------------------|-----------------------------|-------------|---------------------------------|------|---------------------------------|------|---------|---|
|                            |            | 0-3"                  | AU                         |                                   |                             |             |                                 |      |                                 |      |         | Asphalt   |
|                            | ND         | 1                     | SS                         | SM                                |                             |             |                                 |      |                                 |      |         | SILTY SAND: Brown (5/3), 25-30% silt, fine-grained, poorly graded, moderately firm, moderate plasticity, dominantly quartz sand, damp, odorless.  |
|                            | ND         | 5                     | SS                         | ML                                |                             |             |                                 |      |                                 |      |         | SILT: Brown (5/3), fine-grained, very firm, moderate plasticity, damp, odorless.  |
|                            | ND         | 7                     | SS                         | SM                                |                             |             |                                 |      |                                 |      |         | SILTY SAND: Brown (5/3), 10-15% silt, fine to medium-grained, moderately well graded, subangular, firm, dominantly quartz sand, damp, odorless.   |
|                            | ND         | 10                    | SS                         | SW                                |                             |             |                                 |      |                                 |      |         | GRAVELY SAND: Light brown (6/4), 15-20% pebble to cobble gravel (dominantly quartz and feldspar), medium to coarse-grained, moderately well graded, subangular, moderately loose, dominantly quartz and feldspar, damp, odorless. |
|                            | ND         | 15'                   | SS                         | SW                                |                             |             |                                 |      |                                 |      |         | GRAVELY SAND: Light brown (6/4), 15-20% pebble to cobble gravel, medium to coarse-grained, moderately well graded, subangular, loose, dominantly quartz and feldspar, damp, odorless.   |
|                            | ND         | 20'                   | SS                         | SW                                |                             |             |                                 |      |                                 |      |         | GRAVELY SAND: Light brown (6/4), 20-25% pebble gravel, fine to medium grained, moderately well graded, subangular to subrounded, loose, dominantly quartz and feldspar, damp, odorless.   |
|                            |            | 25'                   | SS                         | SP                                |                             |             |                                 |      |                                 |      |         | GRAVELY SAND: Light brown (6/4), 15-20% pebble gravel, fine- to medium-grained (dominantly fine) poorly graded, subangular to subrounded, loose, dominantly quartz, very moist, odorless.   |



PROJECT NO. 21171.00 DATE 1/23/89  
CLIENT Stoddy Company  
LOCATION 16425 Gale Avenue, Industry, California  
LOGGED BY K. Vernon DRILLER H-FBORING NO.  
SB-6  
Sheet 1  
of 2LOG OF  
EXPLORATORY BORINGField Location of Boring: At northeast corner of  
building between planter curbs.

Ground Elev.: Datum:

Drilling method: Continuous-flight, hollow-stem  
augers.Casing Installation Data: 45 feet of 4" diameter  
Schedule 40 PVC; 15 feet of blank and 30 feet  
of 0.01" screen Hole Dia. 11"

| Drilling<br>Rate<br>FT/MIN | PID<br>OVA | D<br>E<br>P<br>T<br>H | S<br>A<br>M<br>P<br>L<br>E | Soil<br>Group<br>Symbol<br>(uscs) | Litho-<br>Graphic<br>Symbol | Water Level                                       | 25 feet |  |  |  |
|----------------------------|------------|-----------------------|----------------------------|-----------------------------------|-----------------------------|---|---------|--|--|--|
|                            |            |                       |                            |                                   |                             | Time  |         |  |  |  |
|                            |            |                       |                            |                                   |                             | Date  | 1/23/89 |  |  |  |
|                            |            |                       |                            |                                   |                             | DESCRIPTION                                       |         |  |  |  |
|                            |            | 0-3"                  | AU                         |                                   |                             | Asphalt   |         |  |  |  |
|                            | ND         | 1'                    | SS                         | SM                                |                             | SILTY SAND: Brown (5/3), 20-25% silt, fine-       |         |  |  |  |
|                            |            |                       |                            |                                   |                             | grained, poorly graded, moderately firm, mod-     |         |  |  |  |
|                            |            |                       |                            |                                   |                             | erate plasticity, dominantly quartz, damp,        |         |  |  |  |
|                            |            |                       |                            |                                   |                             | odorless.   |         |  |  |  |
|                            | ND         | 5'                    | SS                         | ML                                |                             | SILT: Brown (5/3), very firm, moderate plasti-    |         |  |  |  |
|                            |            |                       |                            |                                   |                             | city, damp, odorless.                             |         |  |  |  |
|                            |            |                       |                            |                                   |                             |   |         |  |  |  |
|                            |            |                       |                            |                                   |                             |   |         |  |  |  |
|                            | ND         | 10'                   | SS                         | SW                                |                             | GRAVELY SAND: Light brown (6/4), 15-20% pebble    |         |  |  |  |
|                            |            |                       |                            |                                   |                             | to cobble gravel (dominantly quartz and feldspar) |         |  |  |  |
|                            |            |                       |                            |                                   |                             | medium to coarse-grained, moderately well graded, |         |  |  |  |
|                            |            |                       |                            |                                   |                             | subangular, moderately loose, dominantly quartz   |         |  |  |  |
|                            |            |                       |                            |                                   |                             | and feldspar, damp, odorless.                     |         |  |  |  |
|                            | ND         | 15'                   | SS                         | SW                                |                             | GRAVELY SAND: Light brown (6/4), 15-20% pebble    |         |  |  |  |
|                            |            |                       |                            |                                   |                             | to cobble gravel, medium- to coarse-grained,      |         |  |  |  |
|                            |            |                       |                            |                                   |                             | moderately well graded, subangular, loose,        |         |  |  |  |
|                            |            |                       |                            |                                   |                             | dominantly quartz and feldspar, damp, odorless.   |         |  |  |  |
|                            |            |                       |                            |                                   |                             |   |         |  |  |  |
|                            | ND         | 20'                   | SS                         | SW                                |                             | GRAVELY SAND: Light brown (6/4), 20-25% pebble    |         |  |  |  |
|                            |            |                       |                            |                                   |                             | gravel, fine- to medium-grained, moderately well  |         |  |  |  |
|                            |            |                       |                            |                                   |                             | well graded, subangular to subrounded, loose,     |         |  |  |  |
|                            |            |                       |                            |                                   |                             | dominantly quartz and feldspar, damp, odorless.   |         |  |  |  |
|                            |            |                       |                            |                                   |                             |   |         |  |  |  |
|                            | ND         | 25'                   | SS                         | SP                                |                             | GRAVELY SAND: Light brown (6/4), 10-15% pebble    |         |  |  |  |
|                            |            |                       |                            |                                   |                             | gravel, fine-grained, poorly graded, subrounded,  |         |  |  |  |
|                            |            |                       |                            |                                   |                             | loose, dominantly quartz, wet, odorless.          |         |  |  |  |
|                            |            |                       |                            |                                   |                             |   |         |  |  |  |
|                            |            | 26-46*                | AU                         |                                   |                             | GRAVELY SAND: Brown (6/4), 10-15% pebble gravel,  |         |  |  |  |
|                            |            |                       |                            |                                   |                             | fine- to medium-grained (dominantly fine), poorly |         |  |  |  |
|                            |            |                       |                            |                                   |                             | graded, subrounded, loose, dominantly quartz,     |         |  |  |  |
|                            |            |                       |                            |                                   |                             | wet, odorless.                                    |         |  |  |  |





PROJECT NO. 21171.00 DATE 1/23/89  
 CLIENT Stoody Company  
 LOCATION 16425 Gale Avenue, Industry, California  
 LOGGED BY K. Vernon DRILLER H-F

BORING NO.  
 SB-7  
 Sheet 1  
 of 2

LOG OF  
EXPLORATORY BORING

Field Location of Boring: NE of main building  
near north property line

Ground Elev.: \_\_\_\_\_ Datum: \_\_\_\_\_

Drilling method: Continuous-flight, hollow-stem  
augers.

Casing Installation Data: 45 feet of 4" diameter  
Schedule 40 PVC; 15 feet of blank and 30 feet  
of 0.01" screen Hole Dia. 11"

| Drilling<br>Rate<br>FT/MIN | PID<br>OVA | D<br>E<br>P<br>T<br>H | S<br>A<br>M<br>P<br>L<br>E | Soil<br>Group<br>Symbol<br>(uscs) | Litho-<br>Graphic<br>Symbol | Water Level                                       | 24 feet |  |  |  |
|----------------------------|------------|-----------------------|----------------------------|-----------------------------------|-----------------------------|---|---------|--|--|--|
|                            |            |                       |                            |                                   |                             | Time  |         |  |  |  |
|                            |            |                       |                            |                                   |                             | Date  | 1/23/89 |  |  |  |
|                            |            |                       |                            |                                   |                             | DESCRIPTION                                       |         |  |  |  |
|                            |            | 0-3"                  | AU                         |                                   |                             | Asphalt   |         |  |  |  |
|                            | ND         | 1'                    | SS                         | SM                                |                             | SILTY SAND: Brown (5/3), 15-20% silt, fine-       |         |  |  |  |
|                            |            |                       |                            |                                   |                             | grained, poorly graded, moderately firm, mod-     |         |  |  |  |
|                            |            |                       |                            |                                   |                             | erate plasticity, dominantly quartz, damp,        |         |  |  |  |
|                            |            |                       |                            |                                   |                             | odorless.   |         |  |  |  |
|                            | ND         | 5'                    | SS                         | ML                                |                             | SILT: Brown (5/3), very firm, moderate plasti-    |         |  |  |  |
|                            |            |                       |                            |                                   |                             | city, damp, odorless.                             |         |  |  |  |
|                            |            |                       |                            |                                   |                             |   |         |  |  |  |
|                            |            |                       |                            |                                   |                             |   |         |  |  |  |
|                            | ND         | 10'                   | SS                         | SW                                |                             | GRAVELLY SAND: Light brown (6/4), 15-20% pebble   |         |  |  |  |
|                            |            |                       |                            |                                   |                             | gravel (dominantly quartz and feldspar), medium   |         |  |  |  |
|                            |            |                       |                            |                                   |                             | to coarse grained, moderately well graded,        |         |  |  |  |
|                            |            |                       |                            |                                   |                             | subangular, moderately loose, dominantly quartz   |         |  |  |  |
|                            |            |                       |                            |                                   |                             | and feldspar, damp, odorless.                     |         |  |  |  |
|                            | ND         | 15'                   | SS                         | SW                                |                             | GRAVELLY SAND: Light brown (6/4), 20-25% pebble   |         |  |  |  |
|                            |            |                       |                            |                                   |                             | to cobble gravel, coarse to medium grained,       |         |  |  |  |
|                            |            |                       |                            |                                   |                             | moderately well graded, subangular, loose,        |         |  |  |  |
|                            |            |                       |                            |                                   |                             | dominantly quartz and feldspar, damp, odorless.   |         |  |  |  |
|                            |            |                       |                            |                                   |                             |   |         |  |  |  |
|                            | ND         | 20'                   | SS                         | SW                                |                             | GRAVELY SAND: Light brown (6/4), 20-25% pebble    |         |  |  |  |
|                            |            |                       |                            |                                   |                             | to cobble gravel, fine-to medium-grained, mod-    |         |  |  |  |
|                            |            |                       |                            |                                   |                             | erately well graded, subrounded, loose, dom-      |         |  |  |  |
|                            |            |                       |                            |                                   |                             | inantly quartz and feldspar, damp, odorless.      |         |  |  |  |
|                            |            |                       |                            |                                   |                             |   |         |  |  |  |
|                            | ND         | 25'                   | SS                         | SP                                |                             | GRAVELY SAND: Light brown (6/4), 10-15% pebble    |         |  |  |  |
|                            |            |                       |                            |                                   |                             | gravel, fine- to medium-grained (dominantly fine) |         |  |  |  |
|                            |            |                       |                            |                                   |                             | poorly graded, subrounded, loose, dominantly      |         |  |  |  |
|                            |            |                       |                            |                                   |                             | quartz, wet, odorless.                            |         |  |  |  |
|                            |            | 26-46'                | AU*                        | SP                                |                             | GRAVELY SAND: Brown (6/4), 10-15% pebble gravel,  |         |  |  |  |
|                            |            |                       |                            |                                   |                             | fine to medium-grained (dominantly fine), poorly  |         |  |  |  |
|                            |            |                       |                            |                                   |                             | graded, subrounded, loose, dominantly quartz,     |         |  |  |  |



## Appendix C

**APPENDIX C**  
**WELL COMPLETION DIAGRAMS**

# WELL DETAILS

PROJECT NUMBER 21171.00

BORING / WELL NO. MW-1

PROJECT NAME Stoody Company


TOP OF CASING ELEV. 352.18 feet

COUNTY Los Angeles

GROUND SURFACE ELEV. \_\_\_\_\_

WELL PERMIT NO. \_\_\_\_\_

DATUM MSL



## EXPLORATORY BORING

a. Total depth 46 ft.

b. Diameter 11 in.

Drilling method Hollow-stemmed augers

## WELL CONSTRUCTION

c. Casing length 45 ft.

Material Schedule 40 PVC

d. Diameter 4 in.

e. Depth to top perforations 15 ft.

f. Perforated length 30 ft.

Perforated interval from 15 to 45 ft.

Perforation type screen

Perforation size 0.01"

g. Surface seal 1 ft.

Seal material Concrete with a cement outer apron.

h. Backfill 9 ft.

Backfill material cement/granular bentonite\*

i. Seal 3 ft.

Seal material "Peltonite" Wyoming bentonite pellets

j. Gravel pack 33 ft.

Pack material #2/12 Monterey Sand\*\*

k. Bottom seal NA ft.

Seal material NA

l. Casing height 0 ft.

m. Protective casing diameter 13 in.


\* NL Baroid "Benseal" granular bentonite

\*\* RMC Lonestar Lapis Luster #2/12 Monterey sand.

# WELL DETAILS

PROJECT NUMBER 21171.00  
 PROJECT NAME Stoody Company  
 COUNTY Los Angeles  
 WELL PERMIT NO. ---

BORING / WELL NO. MW-2  
 TOP OF CASING ELEV. 351.12 feet  
 GROUND SURFACE ELEV. ---  
 DATUM MSL



## EXPLORATORY BORING

a. Total depth 46 ft.  
 b. Diameter 11 in.  
 Drilling method Hollow-stemmed augers

## WELL CONSTRUCTION

c. Casing length 45 ft.  
 Material Schedule 40 PVC  
 d. Diameter 4 in.  
 e. Depth to top perforations 15 ft.  
 f. Perforated length 30 ft.  
 Perforated interval from 15 to 45 ft.  
 Perforation type screen  
 Perforation size 0.01"  
 g. Surface seal 1 ft.  
 Seal material Concrete with a cement  
 outer apron.  
 h. Backfill 8.5 ft.  
 Backfill material Cement/Granular bentonite\*  
 i. Seal 3 ft.  
 Seal material "Peltonite" Wyoming bentonite  
 pellets  
 j. Gravel pack 33½ ft.  
 Pack material #2/12 Monterey sand  
 k. Bottom seal NA ft.  
 Seal material NA  
 l. Casing height -- ft.  
 m. Protective casing diameter 12 in.

\* NL Baroid "Benseal" granular bentonite

\*\* RMC Lonestar Lapis Luster #2/12 Monterey sand.

# WELL DETAILS

PROJECT NUMBER 21171.00

BORING / WELL NO. MW-3

PROJECT NAME Stoody Company


TOP OF CASING ELEV. 349.34 feet

COUNTY Los Angeles

GROUND SURFACE ELEV. --

WELL PERMIT NO. --

DATUM MSL



## EXPLORATORY BORING

a. Total depth 46 ft.

b. Diameter 11 in.

Drilling method Hollow-stemmed augers

## WELL CONSTRUCTION

c. Casing length 45 ft.

Material Schedule 40 PVC, 4"

d. Diameter 4 in.

e. Depth to top perforations 15 ft.

f. Perforated length 30 ft.

Perforated interval from 15 to 45 ft.

Perforation type screen

Perforation size 0.01"

g. Surface seal 1 ft.

Seal material Neat cement

h. Backfill 7 ft.

Backfill material Cement/sand/powdered bentonite

i. Seal 3 ft.

Seal material "Peltonite" Wyoming bentonite pellets

j. Gravel pack 34 ft.

Pack material #2/12 Monterey Sand\*

k. Bottom seal NA ft.

Seal material NA

l. Casing height 0 ft.


m. Protective casing diameter 12 in.

\* RMC Lonestar Lapis Luster #2/12 Monterey Sand.

# WELL DETAILS

PROJECT NUMBER 21171.00  
 PROJECT NAME Stoody Company  
 COUNTY Los Angeles  
 WELL PERMIT NO. --

BORING / WELL NO. MW-4  
 TOP OF CASING ELEV. 353.55'  
 GROUND SURFACE ELEV. --  
 DATUM MSL



## EXPLORATORY BORING

a. Total depth 46 ft.  
 b. Diameter 11 in.  
 Drilling method Hollow-stemmed augers

## WELL CONSTRUCTION

c. Casing length 44.92 ft.  
 Material Schedule 40 PVC  
 d. Diameter 4 in.  
 e. Depth to top perforations 14.92 ft.  
 f. Perforated length 30 ft.  
 Perforated interval from 15 to 45 ft.  
 Perforation type Slotted  
 Perforation size 0.01"  
 g. Surface seal 1 ft.  
 Seal material Concrete with a cement apron  
 h. Backfill 6 ft.  
 Backfill material Cement/Granular bentonite\*  
 i. Seal 3 ft.  
 Seal material "Peltonite" Wyoming bentonite pellets  
 j. Gravel pack 35 ft.  
 Pack material #2/12 Monterey sand\*\*  
 k. Bottom seal NA ft.  
 Seal material NA  
 l. Casing height 0 ft.  
 m. Protective casing diameter 12 in.

\* NL Baroid "Benseal" granular bentonite

\*\* RMC Lonestar Lapis Luster #2/12 Monterey sand.



## Appendix D

**APPENDIX D**  
**WATER SAMPLING FIELD SURVEY FORM**

## CLAYTON ENVIRONMENTAL CONSULTANTS, INC.

## WATER SAMPLING FIELD SURVEY FORM

Job #21171.00

Site: Stooddy

Date: 2/2/89

Well # MW-1

Sampling Team: Ken Vernon

Sampling Method: Hand bailing with teflon bailer

Field Conditions: Rainy and cold.

Describe equipment D-Con before sampling this well: TSP and tap water wash and tap water double rinse.

Total Depth  
of Well: 45 feet Time: 06.45Depth to Water  
Water Before Pumping: 25.14 feet

| Height of<br>Water<br>Column: |      | * | <u>Diameter</u> |                            | Volume | * | Purge<br>Factor | Volume to<br>Purge |
|-------------------------------|------|---|-----------------|----------------------------|--------|---|-----------------|--------------------|
|                               |      |   | 2-inch          | 4-inch                     |        |   |                 |                    |
| 19.86                         | feet | * | .16             | = 12.9                     | gal    | * | 3               | =38.7 gallons      |
| Depth Purging From: 27        |      |   | feet            | Time Purging Begins: 06:50 |        |   |                 |                    |

## Notes on Initial Discharge:

| <u>Time</u> | <u>Volume Purged</u> | <u>pH</u> | <u>Conductivity</u> | <u>T</u> | <u>Notes</u>                              |
|-------------|----------------------|-----------|---------------------|----------|---|
| 07:00       | 5 gal.               | 6.25      | 1005us              | 20°C     | Light brown, moderate turbidity, odorless |
| 07:20       | 5 gal.               | 6.20      | 1050us              | 20°C     | Light brown, moderate turbidity, odorless |
| 07:50       | 5 gal.               | 6.20      | 1040us              | 20°C     | Light brown, moderate turbidity, odorless |
| 08:25       | 5 gal.               | 6.28      | 1055us              | 20°C     | Light brown, moderate turbidity, odorless |
| 08:40       | 5 gal.               | 6.30      | 1060us              | 20°C     | Light brown, moderate turbidity, odorless |
| 09:10       | 5 gal.               | 6.20      | 1050us              | 20°C     | Light brown, moderate turbidity, odorless |
| 09:25       | 5 gal.               | 6.20      | 1049us              | 20°C     | Light brown, moderate turbidity, odorless |
| 09:50       | 5 gal.               | 6.25      | 1040us              | 20°C     | Light brown, moderate turbidity, odorless |

**CLAYTON ENVIRONMENTAL CONSULTANTS, INC.**

**WATER SAMPLING FIELD SURVEY FORM  
(CONTINUED)**

**Time Field Parameter Measurement Begins: 10:00**

|              | <u>Rep #1</u> | <u>Rep #2</u> | <u>Rep #3</u> | <u>Rep #4</u> |
|--------------|---------------|---------------|---------------|---------------|
| pH           | 6.20          | 6.25          | 6.20          |               |
| Conductivity | 1050us        | 1045us        | 1048us        |               |
| T°C          | 20°C          | 20°C          | 20°C          |               |

**Pre-Sample Collection Gallons Purged: 40 gallons**

**Time Sample Collection Begins: 10:10**

**Time Sample Collection Ends: 10:15**

**Total Gallons Purged: 41**

**Comments:**

## CLAYTON ENVIRONMENTAL CONSULTANTS, INC.

## WATER SAMPLING FIELD SURVEY FORM

Job # 21171.00

Site: Stooddy Company

Date: 3/28/89

Well # MW-4

Sampling Team: Ken Vernon

Sampling Method: Hand bailing with teflon bailer

Field Conditions: Cloudy and cool.

Describe equipment D-Con before sampling this well: TSP and tap water wash followed by a double tap water rinse.

Total Depth  
of Well: 53.92 feet

Time: 09:15

Depth to Water  
Water Before Pumping: 26.30 feet

| Height of<br>Water<br>Column: | feet | * | <u>Diameter</u> |        | <u>Volume</u> | * | <u>Purge<br/>Factor</u> | <u>Volume to<br/>Purge</u> |
|-------------------------------|------|---|-----------------|--------|---------------|---|-------------------------|----------------------------|
|                               |      |   | 2-inch          | 4-inch |               |   |                         |                            |
| 27.62                         | feet | * | .16             | .65    | = 17.95 gal   | * | 3                       | = 53.86 gallons            |

Depth Purging From: 28

feet

Time Purging Begins: 09:20

Notes on Initial Discharge: Medium brown, moderately high turbidity; suspended silt and fine sand, odorless.

| <u>Time</u> | <u>Volume Purged</u> | <u>pH</u> | <u>Conductivity</u> | <u>T</u> | <u>Notes</u>                                       |
|-------------|----------------------|-----------|---------------------|----------|--|
| 09:25       | 10 gal.              | 6.65      | 1095us              | 28.5 °C  | Medium brown, moderately high turbidity, odorless  |
| 09:50       | 20 gal.              | 6.70      | 1100us              | 28.5 °C  | Medium brown, moderately high turbidity, odorless. |
| 10:35       | 30 gal.              | 6.71      | 1100us              | 28.5 °C  | Light brown, moderate turbidity, odorless          |
| 11:10       | 40 gal.              | 6.60      | 1085us              | 28.5 °C  | Light brown, moderate turbidity, odorless          |
| 11:45       | 50 gal.              | 6.56      | 1100us              | 29 °C    | Light brown, moderate turbidity, odorless          |
| 12:20       | 55 gal.              | 6.55      | 1200us              | 29 °C    | Light brown, low turbidity, odorless               |

CLAYTON ENVIRONMENTAL CONSULTANTS, INC.

WATER SAMPLING FIELD SURVEY FORM  
(CONTINUED)

Time Field Parameter Measurement Begins: 12:30

|              | <u>Rep #1</u> | <u>Rep #2</u> | <u>Rep #3</u> | <u>Rep #4</u> |
|--------------|---------------|---------------|---------------|---------------|
| pH           | 6.56          | 5.50          | 6.52          |               |
| Conductivity | 1210us        | 1200us        | 1208us        |               |
| T°C          | 29°C          | 29°C          | 29°C          |               |

Pre-Sample Collection Gallons Purged: 55

Time Sample Collection Begins: 12:35

Time Sample Collection Ends: 12:42

Total Gallons Purged: 56

Comments:

## CLAYTON ENVIRONMENTAL CONSULTANTS, INC.

## WATER SAMPLING FIELD SURVEY FORM

Job # 21171.00

Site: Stooddy

Date: 2/2/89

Well #MW-2

Sampling Team: Ken Vernon

Sampling Method: Hand bailing with teflon bailer

Field Conditions: Rainy and cold.

Describe equipment D-Con before sampling this well: TSP and tap water wash followed by a tap water double rinse.

Total Depth  
of Well: 45

feet

Time: 10:20

Depth to Water

Water Before Pumping: 24.11

Height of  
Water

Column: 20.89

feet

| <u>Diameter</u> |        | <u>Volume</u> |
|-----------------|--------|---------------|
| 2-inch          | 4-inch |               |
| *               | .16    | .65 = 13.58   |

gal

Purge  
Factor

3

Volume to  
Purge

= 40.74 gal.

Depth Purging From: 26

feet

Time Purging Begins: 10:20

Notes on Initial Discharge: Light brown, moderate turbidity, suspended silt and fine sand, odorless.

| <u>Time</u> | <u>Volume Purged</u> | <u>pH</u> | <u>Conductivity</u> | <u>T</u> | <u>Notes</u>                              |
|-------------|----------------------|-----------|---------------------|----------|---|
| 10:25       | 5 gal.               | 6.40      | 1100us              | 20°C     | Light brown, moderate turbidity, odorless |
| 10:40       | 5 gal.               | 6.45      | 1100us              | 20°C     | Light brown, moderate turbidity, odorless |
| 10:55       | 5 gal.               | 6.40      | 1080us              | 20°C     | Light brown, moderate turbidity, odorless |
| 11:15       | 5 gal.               | 6.50      | 1085us              | 20°C     | Light brown, moderate turbidity, odorless |
| 11:30       | 5 gal.               | 6.52      | 1105us              | 20°C     | Light brown, moderate turbidity, odorless |
| 11:50       | 5 gal.               | 6.50      | 1110us              | 20°C     | Light brown, low turbidity, odorless      |
| 12:15       | 5 gal.               | 6.55      | 1118us              | 20°C     | Light brown, low turbidity, odorless      |
| 12:40       | 5 gal.               | 6.50      | 1120us              | 20°C     | Light brown, low turbidity, odorless      |
| 13:10       | 5 gal.               | 6.45      | 1100us              | 20°C     | Light brown, low turbidity, odorless      |

**CLAYTON ENVIRONMENTAL CONSULTANTS, INC.**

**WATER SAMPLING FIELD SURVEY FORM  
(CONTINUED)**

Time Field Parameter Measurement Begins: 13:20

|              | <u>Rep #1</u> | <u>Rep #2</u> | <u>Rep #3</u> | <u>Rep #4</u> |
|--------------|---------------|---------------|---------------|---------------|
| pH           | 6.48          | 6.50          | 6.45          |               |
| Conductivity | 1110us        | 1105us        | 1112us        |               |
| T°C          | 20°C          | 20°C          | 20°C          |               |

Pre-Sample Collection Gallons Purged: 45

Time Sample Collection Begins: 13:35

Time Sample Collection Ends: 13:50

Total Gallons Purged: 46

Comments:



## CLAYTON ENVIRONMENTAL CONSULTANTS, INC.

## WATER SAMPLING FIELD SURVEY FORM

Job # 21171.00

Site: Stoodly

Date: 2/2/89

Well # MW-3

Sampling Team: Ken Vernon

Sampling Method: Hand bailing with teflon bailer

Field Conditions: Rainy and cold

Describe equipment D-Con before sampling this well: TSP and tap water rinse followed by a double tap water rinse.

|                                     |      |                                  |  |
|-------------------------------------|------|----------------------------------|--|
| Total Depth<br>of Well: 45          | feet | Time: 13:50                      | Depth to Water<br>Water Before Pumping: 26.32 feet |
| Height of<br>Water<br>Column: 13.68 | feet | * .16                            | * 3 = 36.42  |
|                                     |      | <u>Diameter</u><br>2-inch 4-inch | <u>Purge</u><br><u>Factor</u>                      |
|                                     |      | .65 = 12.14                      | <u>Volume</u><br>gal                               |
| Depth Purging From: 28              | feet | Time Purging Begins: 14:00       |  |

Notes on Initial Discharge: Light brown, moderate turbidity; suspended silt and fine sand, odorless.

| <u>Time</u> | <u>Volume Purged</u> | <u>pH</u> | <u>Conductivity</u> | <u>T</u> | <u>Notes</u>                              |
|-------------|----------------------|-----------|---------------------|----------|---|
| 14:15       | 5 gal.               | 6.50      | 1085us              | 20°C     | Light brown, moderate turbidity, odorless |
| 14:25       | 5 gal.               | 6.58      | 1090us              | 20°C     | Light brown, moderate turbidity, odorless |
| 14:35       | 5 gal.               | 6.76      | 1100us              | 20°C     | Light brown, moderate turbidity, odorless |
| 14:50       | 5 gal.               | 6.69      | 1095us              | 20°C     | Light brown, moderate turbidity, odorless |
| 15:05       | 5 gal.               | 6.58      | 1089us              | 20°C     | Light brown, moderate turbidity, odorless |
| 15:20       | 5 gal.               | 6.55      | 1100us              | 20°C     | Light brown, low turbidity, odorless      |
| 15:40       | 5 gal.               | 6.50      | 1105us              | 20°C     | Light brown, low turbidity, odorless      |
| 15:55       | 5 gal.               | 6.52      | 1110us              | 20°C     | Light brown, moderate turbidity, odorless |

**CLAYTON ENVIRONMENTAL CONSULTANTS, INC.**

**WATER SAMPLING FIELD SURVEY FORM  
(CONTINUED)**

Time Field Parameter Measurement Begins: 16:05

|              | <u>Rep #1</u> | <u>Rep #2</u> | <u>Rep #3</u> | <u>Rep #4</u> |
|--------------|---------------|---------------|---------------|---------------|
| pH           | 6.50          | 6.55          | 6.52          |               |
| Conductivity | 1100us        | 1105us        | 1095us        |               |
| T °C         | 20 °C         | 20 °C         | 20 °C         |               |

Pre-Sample Collection Gallons Purged: 40

Time Sample Collection Begins: 16:10


Time Sample Collection Ends: 16:20

Total Gallons Purged: 41


Comments:



**APPENDIX E**  
**WELL SURVEY DIAGRAM**



1" = 50'




6-24 - D.C. Mon. in N/10 sec. City of  
 514 City Ave.  
 (City of Monterey)



| Civic Engineer  | Monterey Hill Survey  |
|---|---|
| David Chang REC 15873<br>1425 Broadway, San Francisco<br>City of Monterey, CA 93940<br>(805) 399-6933 | The Survey Company<br>1425 City Avenue<br>City of Monterey<br>Calif., 93940<br>(408) 948-0710 |

## Appendix F

**APPENDIX F**  
**GROUNDWATER FLOW DIRECTION CALCULATION**



Scale: 1 inch = 100 feet

Standard "3-point problem"

Assumes groundwater surface is a planar feature.

Strike is groundwater contour direction; dip is groundwater flow direction

Dashed lines are groundwater lines with elevations of groundwater table with respect to mean sea level.

Calculations on accompanying page.

Clayton Environmental Consultants, Inc.

GROUNDWATER FLOW DIRECTION CALCULATION

Stoody Company

Project No. 21171.00 6/89



# GROUNDWATER FLOW DIRECTION AND CONTOUR CALCULATIONS

## DISTANCE BETWEEN WELLS

- (1) MW-1 to MW-2 (LEG 1); 107.11'
- (2) MW-1 to MW-3 (LEG 2); 606.21'
- (3) MW-2 to MW-3 (LEG 3); 613.34'

## CHANGE IN ELEVATION OF WATER TABLE BETWEEN WELLS

- (1) MW-1 to MW-2; 0.03'
- (2) MW-1 to MW-3; 4.02'
- (3) MW-2 to MW-3; 3.99'

### (1) FLOW DIRECTION CALCULATION:

$$\frac{.03}{4.02} \times 6.0621'' = 0.045'' \text{ (DISTANCE FROM MW-1 to 327.01' ELEVATION ALONG "LEG (2)")}.$$

### (2) 326' CONTOUR CALCULATION:

$$\frac{1.01}{3.99} \times 6.1334'' = 1.55''$$

$$\frac{1.04}{4.02} \times 6.0621'' = 1.568''$$

### (3) 325' CONTOUR CALCULATION:

$$\frac{2.01}{3.99} \times 6.1334'' = 3.089''$$

$$\frac{2.04}{4.02} \times 6.0621'' = 3.076''$$

### (4) 324' CONTOUR CALCULATION:

$$\frac{3.01}{3.99} \times 6.1334'' = 4.63''$$

$$\frac{3.04}{4.02} \times 6.0621'' = 4.58''$$

### (5) 323' CONTOUR CALCULATION:

$$\frac{4.01}{3.99} \times 6.1334'' = 6.14''$$

$$\frac{4.04}{4.02} \times 6.0621'' = 6.09''$$

## Appendix G

## **APPENDIX G**

### **LABORATORY ANALYTICAL RESULTS AND CHAIN-OF-CUSTODY**

WEST COAST ANALYTICAL SERVICE, INC.

CLAYTON ENVIRONMENTAL CONSULTANTS  
Mr. Ken Vernon

Job # 12126  
March 21, 1989

---

LABORATORY REPORT

---

TABLE I

Parts Per Million (mg/Kg)

| <u>Sample I.D.</u> | <u>Total Petroleum Hydrocarbons</u> |
|--------------------|-------------------------------------|
| Stoody, MW-4,5'    | ND                                  |
| Stoody, MW-4,10'   | ND                                  |
| Stoody, MW-4,15'   | ND                                  |
| Stoody, MW-4,20'   | ND                                  |
| Stoody, MW-4,25'   | ND                                  |
| Detection Limit    | 10                                  |

ND-Not Detected

Date Analyzed: 3-9-89

CLIENT: CLAYTON ENVIRONMENTAL  
WCAS JOB #: 12126

SAMPLE: STODY, MW-4, 5'

DATE RECEIVED: 03/08/89  
DATE EXTRACTED: 03/15/89  
DATE ANALYZED: 03/15/89

RUN NUMBER: 12126V1  
SAMPLE AMOUNT: 1.0G  
MATRIX: SOIL

VOLATILE ORGANICS (EPA 624/8240)

UNITS: UG/KG (PPB)

| CAS #      | COMPOUND                    | CONCENTRATION | DET LIMIT |
|------------|-----------------------------|---------------|-----------|
| 67-64-1    | ACETONE                     | 30.           | 30.       |
| 71-43-2    | BENZENE                     | ND            | 5.        |
| 75-27-4    | BROMODICHLOROMETHANE        | ND            | 5.        |
| 75-25-2    | BROMOFORM                   | ND            | 5.        |
| 74-83-9    | BROMOMETHANE                | ND            | 30.       |
| 78-93-3    | 2-BUTANONE (MEK)            | ND            | 30.       |
| 75-15-0    | CARBON DISULFIDE            | ND            | 5.        |
| 56-23-5    | CARBON TETRACHLORIDE        | ND            | 5.        |
| 108-90-7   | CHLOROBENZENE               | ND            | 5.        |
| 75-00-3    | CHLOROETHANE                | ND            | 30.       |
| 110-75-8   | 2-CHLOROETHYL VINYLETHER    | ND            | 50.       |
| 67-66-3    | CHLOROFORM                  | ND            | 5.        |
| 74-87-3    | CHLOROMETHANE               | ND            | 30.       |
| 108-41-8   | CHLOROTOLUENE               | ND            | 5.        |
| 124-48-1   | DIBROMOCHLOROMETHANE        | ND            | 5.        |
| 95-50-1    | 1,2-DICHLOROBENZENE         | ND            | 5.        |
| 541-73-1   | 1,3-DICHLOROBENZENE         | ND            | 5.        |
| 106-46-7   | 1,4-DICHLOROBENZENE         | ND            | 5.        |
| 75-34-3    | 1,1-DICHLOROETHANE          | ND            | 5.        |
| 107-06-2   | 1,2-DICHLOROETHANE          | ND            | 5.        |
| 75-35-4    | 1,1-DICHLOROETHYLENE        | ND            | 5.        |
| 156-59-4   | CIS-1,2-DICHLOROETHYLENE    | ND            | 5.        |
| 156-60-5   | TRANS-1,2-DICHLOROETHYLENE  | ND            | 5.        |
| 78-87-5    | 1,2-DICHLOROPROPANE         | ND            | 5.        |
| 10061-01-5 | CIS-1,3-DICHLOROPROPENE     | ND            | 5.        |
| 10061-02-6 | TRANS-1,3-DICHLOROPROPENE   | ND            | 5.        |
| 100-41-4   | ETHYLBENZENE                | ND            | 5.        |
| 106-93-4   | ETHYLENE DIBROMIDE          | ND            | 5.        |
| 76-13-1    | FREON-TF                    | ND            | 5.        |
| 119-78-6   | 2-HEXANONE                  | ND            | 30.       |
| 75-09-2    | METHYLENE CHLORIDE          | ND            | 30.       |
| 108-10-1   | 4-METHYL-2-PENTANONE (MIBK) | ND            | 30.       |
| 100-42-5   | STYRENE                     | ND            | 5.        |
| 79-34-5    | 1,1,2,2-TETRACHLOROETHANE   | ND            | 5.        |
| 127-18-4   | TETRACHLOROETHYLENE         | ND            | 5.        |
| 109-99-9   | TETRAHYDROFURAN             | ND            | 30.       |
| 108-88-3   | TOLUENE                     | ND            | 5.        |
| 71-55-6    | 1,1,1-TRICHLOROETHANE       | ND            | 5.        |
| 79-00-5    | 1,1,2-TRICHLOROETHANE       | ND            | 5.        |
| 79-01-6    | TRICHLOROETHYLENE           | ND            | 5.        |
| 75-69-4    | TRICHLOROFLUOROMETHANE      | ND            | 5.        |
| 108-05-4   | VINYL ACETATE               | ND            | 30.       |
| 75-01-4    | VINYL CHLORIDE              | ND            | 30.       |
| 95-47-6    | TOTAL XYLENES               | ND            | 5.        |

TENTATIVELY IDENTIFIED COMPOUNDS

CLIENT: CLAYTON ENVIRONMENTAL  
WCAS JOB #: 12126

SAMPLE: STOODY, MW-4, 5'

UNITS: UG/KG (PPB)

| COMPOUND NAME | FRACTION | APPROXIMATE<br>CONCENTRATION |
|---------------|----------|------------------------------|
| =====         |          |                              |
| 1 NONE FOUND  | VOA      |                              |

CLIENT: CLAYTON ENVIRONMENTAL  
WCAS JOB #: 12126

SAMPLE: STOODY, MW-4, 10'

DATE RECEIVED: 03/08/89  
DATE EXTRACTED: 03/15/89  
DATE ANALYZED: 03/15/89

RUN NUMBER: 12126V2  
SAMPLE AMOUNT: 1.0G  
MATRIX: SOIL

VOLATILE ORGANICS (EPA 624/8240)

UNITS: UG/KG (PPB)

| CAS #      | COMPOUND                    | CONCENTRATION | DET LIMIT |
|------------|-----------------------------|---------------|-----------|
| 67-64-1    | ACETONE                     | 34.           | 30.       |
| 71-43-2    | BENZENE                     | ND            | 5.        |
| 75-27-4    | BROMODICHLOROMETHANE        | ND            | 5.        |
| 75-25-2    | BROMOFORM                   | ND            | 5.        |
| 74-83-9    | BROMOMETHANE                | ND            | 30.       |
| 78-93-3    | 2-BUTANONE (MEK)            | ND            | 30.       |
| 75-15-0    | CARBON DISULFIDE            | ND            | 5.        |
| 56-23-5    | CARBON TETRACHLORIDE        | ND            | 5.        |
| 108-90-7   | CHLOROBENZENE               | ND            | 5.        |
| 75-00-3    | CHLOROETHANE                | ND            | 30.       |
| 110-75-8   | 2-CHLOROETHYL VINYLETHER    | ND            | 50.       |
| 67-66-3    | CHLOROFORM                  | ND            | 5.        |
| 74-87-3    | CHLOROMETHANE               | ND            | 30.       |
| 108-41-8   | CHLOROTOLUENE               | ND            | 5.        |
| 124-48-1   | DIBROMOCHLOROMETHANE        | ND            | 5.        |
| 95-50-1    | 1,2-DICHLOROBENZENE         | ND            | 5.        |
| 541-73-1   | 1,3-DICHLOROBENZENE         | ND            | 5.        |
| 106-46-7   | 1,4-DICHLOROBENZENE         | ND            | 5.        |
| 75-34-3    | 1,1-DICHLOROETHANE          | ND            | 5.        |
| 107-06-2   | 1,2-DICHLOROETHANE          | ND            | 5.        |
| 75-35-4    | 1,1-DICHLOROETHYLENE        | ND            | 5.        |
| 156-59-4   | CIS-1,2-DICHLOROETHYLENE    | ND            | 5.        |
| 156-60-5   | TRANS-1,2-DICHLOROETHYLENE  | ND            | 5.        |
| 78-87-5    | 1,2-DICHLOROPROPANE         | ND            | 5.        |
| 10061-01-5 | CIS-1,3-DICHLOROPROPENE     | ND            | 5.        |
| 10061-02-6 | TRANS-1,3-DICHLOROPROPENE   | ND            | 5.        |
| 100-41-4   | ETHYLBENZENE                | ND            | 5.        |
| 106-93-4   | ETHYLENE DIBROMIDE          | ND            | 5.        |
| 76-13-1    | FREON-TF                    | ND            | 5.        |
| 119-78-6   | 2-HEXANONE                  | ND            | 30.       |
| 75-09-2    | METHYLENE CHLORIDE          | ND            | 30.       |
| 108-10-1   | 4-METHYL-2-PENTANONE (MIBK) | ND            | 30.       |
| 100-42-5   | STYRENE                     | ND            | 5.        |
| 79-34-5    | 1,1,2,2-TETRACHLOROETHANE   | ND            | 5.        |
| 127-18-4   | TETRACHLOROETHYLENE         | ND            | 5.        |
| 109-99-9   | TETRAHYDROFURAN             | ND            | 30.       |
| 108-88-3   | TOLUENE                     | ND            | 5.        |
| 71-55-6    | 1,1,1-TRICHLOROETHANE       | ND            | 5.        |
| 79-00-5    | 1,1,2-TRICHLOROETHANE       | ND            | 5.        |
| 79-01-6    | TRICHLOROETHYLENE           | ND            | 5.        |
| 75-69-4    | TRICHLOROFLUOROMETHANE      | ND            | 5.        |
| 108-05-4   | VINYL ACETATE               | ND            | 30.       |
| 75-01-4    | VINYL CHLORIDE              | ND            | 30.       |
| 95-47-6    | TOTAL XYLENES               | ND            | 5.        |

TENTATIVELY IDENTIFIED COMPOUNDS

CLIENT: CLAYTON ENVIRONMENTAL  
WCAS JOB #: 12126

SAMPLE: STOODY, MW-4, 10'

UNITS: UG/KG (PPB)

| COMPOUND NAME | FRACTION | APPROXIMATE<br>CONCENTRATION |
|---------------|----------|------------------------------|
| =====         | =====    | =====                        |
| 1 NONE FOUND  | VOA      |                              |



CLIENT: CLAYTON ENVIRONMENTAL  
WCAS JOB #: 12126

SAMPLE: STOODY, MW-4, 15'

DATE RECEIVED: 03/08/89  
DATE EXTRACTED: 03/15/89  
DATE ANALYZED: 03/15/89

RUN NUMBER: 12126V3  
SAMPLE AMOUNT: 1.0G  
MATRIX: SOIL

VOLATILE ORGANICS (EPA 624/8240)

UNITS: UG/KG (PPB)

| CAS #      | COMPOUND                    | CONCENTRATION | DET LIMIT |
|------------|-----------------------------|---------------|-----------|
| 67-64-1    | ACETONE                     | 37.           | 30.       |
| 71-43-2    | BENZENE                     | ND            | 5.        |
| 75-27-4    | BROMODICHLOROMETHANE        | ND            | 5.        |
| 75-25-2    | BROMOFORM                   | ND            | 5.        |
| 74-83-9    | BROMOMETHANE                | ND            | 30.       |
| 78-93-3    | 2-BUTANONE (MEK)            | ND            | 30.       |
| 75-15-0    | CARBON DISULFIDE            | ND            | 5.        |
| 56-23-5    | CARBON TETRACHLORIDE        | ND            | 5.        |
| 108-90-7   | CHLOROBENZENE               | ND            | 5.        |
| 75-00-3    | CHLOROETHANE                | ND            | 30.       |
| 110-75-8   | 2-CHLOROETHYL VINYLETHER    | ND            | 50.       |
| 67-66-3    | CHLOROFORM                  | ND            | 5.        |
| 74-87-3    | CHLOROMETHANE               | ND            | 30.       |
| 108-41-8   | CHLOROTOLUENE               | ND            | 5.        |
| 124-48-1   | DIBROMOCHLOROMETHANE        | ND            | 5.        |
| 95-50-1    | 1,2-DICHLOROBENZENE         | ND            | 5.        |
| 541-73-1   | 1,3-DICHLOROBENZENE         | ND            | 5.        |
| 106-46-7   | 1,4-DICHLOROBENZENE         | ND            | 5.        |
| 75-34-3    | 1,1-DICHLOROETHANE          | ND            | 5.        |
| 107-06-2   | 1,2-DICHLOROETHANE          | ND            | 5.        |
| 75-35-4    | 1,1-DICHLOROETHYLENE        | ND            | 5.        |
| 156-59-4   | CIS-1,2-DICHLOROETHYLENE    | ND            | 5.        |
| 156-60-5   | TRANS-1,2-DICHLOROETHYLENE  | ND            | 5.        |
| 78-87-5    | 1,2-DICHLOROPROPANE         | ND            | 5.        |
| 10061-01-5 | CIS-1,3-DICHLOROPROPENE     | ND            | 5.        |
| 10061-02-6 | TRANS-1,3-DICHLOROPROPENE   | ND            | 5.        |
| 100-41-4   | ETHYLBENZENE                | ND            | 5.        |
| 106-93-4   | ETHYLENE DIBROMIDE          | ND            | 5.        |
| 76-13-1    | FREON-TF                    | ND            | 5.        |
| 119-78-6   | 2-HEXANONE                  | ND            | 30.       |
| 75-09-2    | METHYLENE CHLORIDE          | ND            | 30.       |
| 108-10-1   | 4-METHYL-2-PENTANONE (MIBK) | ND            | 30.       |
| 100-42-5   | STYRENE                     | ND            | 5.        |
| 79-34-5    | 1,1,2,2-TETRACHLOROETHANE   | ND            | 5.        |
| 127-18-4   | TETRACHLOROETHYLENE         | ND            | 5.        |
| 109-99-9   | TETRAHYDROFURAN             | ND            | 30.       |
| 108-88-3   | TOLUENE                     | ND            | 5.        |
| 71-55-6    | 1,1,1-TRICHLOROETHANE       | ND            | 5.        |
| 79-00-5    | 1,1,2-TRICHLOROETHANE       | ND            | 5.        |
| 79-01-6    | TRICHLOROETHYLENE           | ND            | 5.        |
| 75-69-4    | TRICHLOROFLUOROMETHANE      | ND            | 5.        |
| 108-05-4   | VINYL ACETATE               | ND            | 30.       |
| 75-01-4    | VINYL CHLORIDE              | ND            | 30.       |
| 95-47-6    | TOTAL XYLENES               | ND            | 5.        |

TENTATIVELY IDENTIFIED COMPOUNDS

CLIENT: CLAYTON ENVIRONMENTAL  
WCAS JOB #: 12126

SAMPLE: STOODY, MW-4, 15'

UNITS: UG/KG (PPB)

| COMPOUND NAME | FRACTION | APPROXIMATE<br>CONCENTRATION |
|---------------|----------|------------------------------|
| =====         |          |                              |
| 1 NONE FOUND  | VOA      |                              |

=====WCAS=====

CLIENT: CLAYTON ENVIRONMENTAL  
WCAS JOB #: 12126

SAMPLE: STOODY, MW-4, 20'

DATE RECEIVED: 03/08/89  
DATE EXTRACTED: 03/15/89  
DATE ANALYZED: 03/15/89

RUN NUMBER: 12126V4  
SAMPLE AMOUNT: 1.0G  
MATRIX: SOIL

VOLATILE ORGANICS (EPA 624/8240)

UNITS: UG/KG (PPB)

| CAS #      | COMPOUND                    | CONCENTRATION | DET LIMIT |
|------------|-----------------------------|---------------|-----------|
| 67-64-1    | ACETONE                     | 45.           | 30.       |
| 71-43-2    | BENZENE                     | ND            | 5.        |
| 75-27-4    | BROMODICHLOROMETHANE        | ND            | 5.        |
| 75-25-2    | BROMOFORM                   | ND            | 5.        |
| 74-83-9    | BROMOMETHANE                | ND            | 30.       |
| 78-93-3    | 2-BUTANONE (MEK)            | ND            | 30.       |
| 75-15-0    | CARBON DISULFIDE            | ND            | 5.        |
| 56-23-5    | CARBON TETRACHLORIDE        | ND            | 5.        |
| 108-90-7   | CHLOROBENZENE               | ND            | 5.        |
| 75-00-3    | CHLOROETHANE                | ND            | 30.       |
| 110-75-8   | 2-CHLOROETHYL VINYLETHER    | ND            | 50.       |
| 67-66-3    | CHLOROFORM                  | ND            | 5.        |
| 74-87-3    | CHLOROMETHANE               | ND            | 30.       |
| 108-41-8   | CHLOROTOLUENE               | ND            | 5.        |
| 124-48-1   | DIBROMOCHLOROMETHANE        | ND            | 5.        |
| 95-50-1    | 1,2-DICHLOROBENZENE         | ND            | 5.        |
| 541-73-1   | 1,3-DICHLOROBENZENE         | ND            | 5.        |
| 106-46-7   | 1,4-DICHLOROBENZENE         | ND            | 5.        |
| 75-34-3    | 1,1-DICHLOROETHANE          | ND            | 5.        |
| 107-06-2   | 1,2-DICHLOROETHANE          | ND            | 5.        |
| 75-35-4    | 1,1-DICHLOROETHYLENE        | ND            | 5.        |
| 156-59-4   | CIS-1,2-DICHLOROETHYLENE    | ND            | 5.        |
| 156-60-5   | TRANS-1,2-DICHLOROETHYLENE  | ND            | 5.        |
| 78-87-5    | 1,2-DICHLOROPROPANE         | ND            | 5.        |
| 10061-01-5 | CIS-1,3-DICHLOROPROPENE     | ND            | 5.        |
| 10061-02-6 | TRANS-1,3-DICHLOROPROPENE   | ND            | 5.        |
| 100-41-4   | ETHYLBENZENE                | ND            | 5.        |
| 106-93-4   | ETHYLENE DIBROMIDE          | ND            | 5.        |
| 76-13-1    | FREON-TF                    | ND            | 5.        |
| 119-78-6   | 2-HEXANONE                  | ND            | 30.       |
| 75-09-2    | METHYLENE CHLORIDE          | 52.           | 30.       |
| 108-10-1   | 4-METHYL-2-PENTANONE (MIBK) | ND            | 30.       |
| 100-42-5   | STYRENE                     | ND            | 5.        |
| 79-34-5    | 1,1,2,2-TETRACHLOROETHANE   | ND            | 5.        |
| 127-18-4   | TETRACHLOROETHYLENE         | ND            | 5.        |
| 109-99-9   | TETRAHYDROFURAN             | ND            | 30.       |
| 108-88-3   | TOLUENE                     | ND            | 5.        |
| 71-55-6    | 1,1,1-TRICHLOROETHANE       | ND            | 5.        |
| 79-00-5    | 1,1,2-TRICHLOROETHANE       | ND            | 5.        |
| 79-01-6    | TRICHLOROETHYLENE           | ND            | 5.        |
| 75-69-4    | TRICHLOROFLUOROMETHANE      | ND            | 5.        |
| 108-05-4   | VINYL ACETATE               | ND            | 30.       |
| 75-01-4    | VINYL CHLORIDE              | ND            | 30.       |
| 95-47-6    | TOTAL XYLENES               | ND            | 5.        |

TENTATIVELY IDENTIFIED COMPOUNDS

CLIENT: CLAYTON ENVIRONMENTAL  
WCAS JOB #: 12126

SAMPLE: STOODY, MW-4, 20'

UNITS: UG/KG (PPB)

| COMPOUND NAME | FRACTION | APPROXIMATE<br>CONCENTRATION |
|---------------|----------|------------------------------|
| =====         |          |                              |
| 1 NONE FOUND  | VOA      |                              |

WCAS

CLIENT: CLAYTON ENVIRONMENTAL  
WCAS JOB #: 12126

SAMPLE: STOODY, MW-4, 25'

DATE RECEIVED: 03/08/89  
DATE EXTRACTED: 03/15/89  
DATE ANALYZED: 03/15/89

RUN NUMBER: 12126V5  
SAMPLE AMOUNT: 1.0G  
MATRIX: SOIL

VOLATILE ORGANICS (EPA 624/8240)

UNITS: UG/KG (PPB)

| CAS #      | COMPOUND                    | CONCENTRATION | DET LIMIT |
|------------|-----------------------------|---------------|-----------|
| 67-64-1    | ACETONE                     | 48.           | 30.       |
| 71-43-2    | BENZENE                     | ND            | 5.        |
| 75-27-4    | BROMODICHLOROMETHANE        | ND            | 5.        |
| 75-25-2    | BROMOFORM                   | ND            | 5.        |
| 74-83-9    | BROMOMETHANE                | ND            | 30.       |
| 78-93-3    | 2-BUTANONE (MEK)            | ND            | 30.       |
| 75-15-0    | CARBON DISULFIDE            | ND            | 5.        |
| 56-23-5    | CARBON TETRACHLORIDE        | ND            | 5.        |
| 108-90-7   | CHLOROBENZENE               | ND            | 5.        |
| 75-00-3    | CHLOROETHANE                | ND            | 30.       |
| 110-75-8   | 2-CHLOROETHYL VINYLETHER    | ND            | 50.       |
| 67-66-3    | CHLOROFORM                  | ND            | 5.        |
| 74-87-3    | CHLOROMETHANE               | ND            | 30.       |
| 108-41-8   | CHLOROTOLUENE               | ND            | 5.        |
| 124-48-1   | DIBROMOCHLOROMETHANE        | ND            | 5.        |
| 95-50-1    | 1,2-DICHLOROBENZENE         | ND            | 5.        |
| 541-73-1   | 1,3-DICHLOROBENZENE         | ND            | 5.        |
| 106-46-7   | 1,4-DICHLOROBENZENE         | ND            | 5.        |
| 75-34-3    | 1,1-DICHLOROETHANE          | ND            | 5.        |
| 107-06-2   | 1,2-DICHLOROETHANE          | ND            | 5.        |
| 75-35-4    | 1,1-DICHLOROETHYLENE        | ND            | 5.        |
| 156-59-4   | CIS-1,2-DICHLOROETHYLENE    | ND            | 5.        |
| 156-60-5   | TRANS-1,2-DICHLOROETHYLENE  | ND            | 5.        |
| 78-87-5    | 1,2-DICHLOROPROPANE         | ND            | 5.        |
| 10061-01-5 | CIS-1,3-DICHLOROPROPENE     | ND            | 5.        |
| 10061-02-6 | TRANS-1,3-DICHLOROPROPENE   | ND            | 5.        |
| 100-41-4   | ETHYLBENZENE                | ND            | 5.        |
| 106-93-4   | ETHYLENE DIBROMIDE          | ND            | 5.        |
| 76-13-1    | FREON-TF                    | ND            | 5.        |
| 119-78-6   | 2-HEXANONE                  | ND            | 30.       |
| 75-09-2    | METHYLENE CHLORIDE          | ND            | 30.       |
| 108-10-1   | 4-METHYL-2-PENTANONE (MIBK) | ND            | 30.       |
| 100-42-5   | STYRENE                     | ND            | 5.        |
| 79-34-5    | 1,1,2,2-TETRACHLOROETHANE   | ND            | 5.        |
| 127-18-4   | TETRACHLOROETHYLENE         | ND            | 5.        |
| 109-99-9   | TETRAHYDROFURAN             | ND            | 30.       |
| 108-88-3   | TOLUENE                     | ND            | 5.        |
| 71-55-6    | 1,1,1-TRICHLOROETHANE       | ND            | 5.        |
| 79-00-5    | 1,1,2-TRICHLOROETHANE       | ND            | 5.        |
| 79-01-6    | TRICHLOROETHYLENE           | ND            | 5.        |
| 75-69-4    | TRICHLOROFLUOROMETHANE      | ND            | 5.        |
| 108-05-4   | VINYL ACETATE               | ND            | 30.       |
| 75-01-4    | VINYL CHLORIDE              | ND            | 30.       |
| 95-47-6    | TOTAL XYLENES               | ND            | 5.        |

TENTATIVELY IDENTIFIED COMPOUNDS

CLIENT: CLAYTON ENVIRONMENTAL  
WCAS JOB #: 12126

SAMPLE: STOODY, MW-4, 25'

UNITS: UG/KG (PPB)

| COMPOUND NAME | FRACTION | APPROXIMATE<br>CONCENTRATION |
|---------------|----------|------------------------------|
| =====         |          |                              |
| 1 NONE FOUND  | VOA      |                              |

WCAS

## Data Reporting Qualifiers

- Value** - If the result is a value greater than or equal to the Detection Limit (DL), the value is reported.
- ND** - Indicates that the compound was analyzed for but not detected. The minimum DL for the sample with the ND is reported based on necessary concentration or dilution actions.
- TR** - Indicates an estimated value. This flag is used when the mass spectral data indicates the presence of a compound that meets the identification criteria but the result is less than the specified DL but greater than zero.

# Clayton

## ENVIRONMENTAL CONSULTANTS

A Marsh & McLennan Company

## REQUEST FOR LABORATORY ANALYTICAL SERVICES

|                      |  |      |   |    |   |
|----------------------|--|------|---|----|---|
| For Clayton Use Only |  | Page | 1 | of | 1 |
| Project No.          |  |      |   |    |   |
| Batch No.            |  |      |   |    |   |
| Client No.           |  |      |   |    |   |
| Date Received        |  |      |   |    |   |
| Date Logged In       |  |      |   |    |   |

Purchase Order No.

Client Job No. 21171.00

SEND INVOICE TO

Name KEN LEBRON  
Company CLAYTON ENVIRONMENTAL Dept. ENG.  
Address 5736 CORPORATE AVE.  
City, State, Zip CYDRESS, CA. 90630-0788

Date Results Required:

Rush Charges Authorized?

☐ Yes ☒ No

Special Instructions: (method, limit of detection, phone results, rush results, etc.)

ESPA METHODS 418.1 AND 8240 MODIFIED

\* Explanation of Preservative:

### CLIENT SAMPLE IDENTIFICATION

DATE SAMPLED

MATRIX/MEDIA

AIR VOLUME (specify units)

Number of Containers

REPORT RESULTS TO

Name Sams  
Company  
Mailing Address  
City, State, Zip  
Telephone No.

(Enter an 'X' in the box below to indicate request; Enter a 'P' if Preservative added)

ANALYSIS REQUESTED

FOR LAB USE ONLY

CHAIN OF CUSTODY  
(if required)  
Relinquished by: Ken LEBRON  
Date/Time 3-7-89 15:45  
Relinquished by: Ken LEBRON  
Date/Time  
Method of Shipment:

Received by:

Received at lab by: Ken LEBRON

Sample condition upon receipt:

Date/Time

Date/Time 3-8/1035

Authorized by: Ken LEBRON  
(Client Signature Must Accompany Request)

Date 3-7-89

DISTRIBUTION:

WHITE - Clayton Laboratory  
YELLOW - Clayton Accounting

Please return completed form and samples to one of the Clayton Environmental Consultants, Inc. labs listed below:

22345 Roothel Drive

Novi, MI 48050

160 Fieldcrest Ave.

Raritan Center  
400 Chastain Center Blvd., N.W.  
Suite 490

1252 Quarry Lane  
Pleasanton, CA 94566

#12126



# Clayton Environmental Consultants, Inc.

P.O. Box 9019 • 1252 Quarry Lane • Pleasanton, CA 94566 • (415) 426-2600

April 12, 1989

Mr. Ken Vernon  
CLAYTON ENVIRONMENTAL CONSULTANTS, INC.  
5736 Corporate Avenue  
P.O. Box 788  
Cypress, CA 90630-0788

Client Ref. No.: 21171.00  
Lab Batch No.: 8903183  
Clayton Project No.: 21171.77  
Client Code No.: 0064


Dear Mr. Vernon:

Attached is our analytical laboratory report for the samples received on March 29, 1989. A copy of the Chain of Custody form acknowledging receipt of these samples is attached.

Please note that any unused portion of the samples will be retained at our facility for approximately 30 days after the date of this report, unless you have requested otherwise.

We appreciate the opportunity to be of assistance to you. If you have any questions, please call Maryann Gambino, Client Services Representative, at (415) 426-2657.

Sincerely,



Ronald H. Peters, CIH  
Manager, Laboratory Services

RHP/tb  
Attachment

EPA METHOD 624  
PURGEABLE ORGANICS

|                  |             |                  |            |
|------------------|-------------|------------------|------------|
| Sample I.D.:     | Stoody MW-4 | Client:          | STOODY CO. |
| Sample Received: | 03/29/89    | Client Ref. No.: | 21171.00   |
| Sample Analyzed: | 03/30/89    | Lab Client Code: | 0471       |
| Sample Matrix:   | Water       | Lab No.:         | 8903183-01 |

| <u>Compound</u>           | <u>Concentration<br/>µg/L (ppb)</u> | <u>Limit of Detection<br/>µg/L (ppb)</u> |
|---------------------------|-------------------------------------|--|
| Chloromethane             | ND                                  | 10                                       |
| Bromomethane              | ND                                  | 4  |
| Vinyl chloride            | ND                                  | 4  |
| Chloroethane              | ND                                  | 4  |
| Methylene chloride        | ND                                  | 10                                       |
| Trichlorofluoromethane    | ND                                  | 3  |
| 1,1-dichloroethene        | 11                                  | 3  |
| 1,1-dichloroethane        | ND                                  | 3  |
| Trans-1,2-dichloroethene  | ND                                  | 3  |
| Chloroform                | ND                                  | 3  |
| 1,2-dichloroethane        | ND                                  | 3  |
| 1,1,1-trichloroethane     | ND                                  | 3  |
| Carbon tetrachloride      | ND                                  | 3  |
| Bromodichloromethane      | ND                                  | 3  |
| 1,2-dichloropropane       | ND                                  | 3  |
| Cis-1,3-dichloropropene   | ND                                  | 3  |
| Trichloroethene           | 44                                  | 4  |
| Benzene                   | ND                                  | 2  |
| Dibromochloromethane      | ND                                  | 2  |
| 1,1,2-trichloroethane     | ND                                  | 3  |
| Trans-1,3-dichloropropene | ND                                  | 5  |
| 2-chloroethylvinylether   | ND                                  | 3  |
| Bromoform                 | ND                                  | 3  |
| 1,1,2,2-tetrachloroethane | ND                                  | 4  |
| Tetrachloroethene         | 55                                  | 4  |
| Toluene                   | ND                                  | 2  |
| Chlorobenzene             | ND                                  | 3  |
| Ethylbenzene              | ND                                  | 3  |
| 1,3-dichlorobenzene       | ND                                  | 3  |
| 1,2-dichlorobenzene       | ND                                  | 3  |
| 1,4-dichlorobenzene       | ND                                  | 3  |
| Freon 113                 | 3                                   | 3  |
| Total Xylenes             | ND                                  | 3  |

ND = Not detected at or above limit of detection.

## EPA METHOD 624

PURGEABLE ORGANICS  
TENTATIVE IDENTIFICATION OF NON-PRIORITY POLLUTANTS

|                  |             |                  |            |
|------------------|-------------|------------------|------------|
| Sample I.D.:     | Stoody MW-4 | Client:          | STOODY CO. |
| Sample Received: | 03/29/89    | Client Ref. No.: | 21171.00   |
| Sample Analyzed: | 03/30/89    | Lab Client Code: | 0471       |
| Sample Matrix:   | Water       | Lab No.:         | 8903183-01 |

| <u>Scan<br/>Number</u> | <u>Compound</u> | <u>Estimated*<br/>Concentration<br/>µg/L (ppb)</u> | <u>Limit of<br/>Detection<br/>(ppb)</u> |
|------------------------|-----------------|--|---|
|------------------------|-----------------|--|---|

No Non-HSL Compounds Found >10% of nearest internal standard

ND = Not detected at or above limit of detection

Tentative Identification based on nearest match to NBS library.

\* Estimated concentration based on peak area response of nearest internal standard.

EPA METHOD 624  
PURGEABLE ORGANICS

|                  |              |                  |            |
|------------------|--------------|------------------|------------|
| Sample I.D.:     | Method Blank | Client:          | STOODY CO. |
| Sample Received: |              | Client Ref. No.: | 21171.00   |
| Sample Analyzed: | 03/30/89     | Lab Client Code: | 0471       |
| Sample Matrix:   | Water        | Lab No.:         | 8903183-MB |

| Compound                  | Concentration<br><u>µg/L (ppb)</u> | Limit of Detection<br><u>µg/L (ppb)</u> |
|---------------------------|------------------------------------|---|
| Chloromethane             | ND                                 | 10                                      |
| Bromomethane              | ND                                 | 4                                       |
| Vinyl chloride            | ND                                 | 4                                       |
| Chloroethane              | ND                                 | 4                                       |
| Methylene chloride        | ND                                 | 10                                      |
| Trichlorofluoromethane    | ND                                 | 3                                       |
| 1,1-dichloroethene        | ND                                 | 3                                       |
| 1,1-dichloroethane        | ND                                 | 3                                       |
| Trans-1,2-dichloroethene  | ND                                 | 3                                       |
| Chloroform                | ND                                 | 3                                       |
| 1,2-dichloroethane        | ND                                 | 3                                       |
| 1,1,1-trichloroethane     | ND                                 | 3                                       |
| Carbon tetrachloride      | ND                                 | 3                                       |
| Bromodichloromethane      | ND                                 | 3                                       |
| 1,2-dichloropropane       | ND                                 | 3                                       |
| Cis-1,3-dichloropropene   | ND                                 | 3                                       |
| Trichloroethene           | ND                                 | 4                                       |
| Benzene                   | ND                                 | 2                                       |
| Dibromochloromethane      | ND                                 | 2                                       |
| 1,1,2-trichloroethane     | ND                                 | 3                                       |
| Trans-1,3-dichloropropene | ND                                 | 5                                       |
| 2-chloroethylvinylether   | ND                                 | 3                                       |
| Bromoform                 | ND                                 | 3                                       |
| 1,1,2,2-tetrachloroethane | ND                                 | 4                                       |
| Tetrachloroethene         | ND                                 | 4                                       |
| Toluene                   | ND                                 | 2                                       |
| Chlorobenzene             | ND                                 | 3                                       |
| Ethylbenzene              | ND                                 | 3                                       |
| 1,3-dichlorobenzene       | ND                                 | 3                                       |
| 1,2-dichlorobenzene       | ND                                 | 3                                       |
| 1,4-dichlorobenzene       | ND                                 | 3                                       |
| Freon 113                 | ND                                 | 3                                       |
| Total Xylenes             | ND                                 | 3                                       |

ND = Not detected at or above limit of detection.

|                  |           |                  |            |
|------------------|-----------|------------------|------------|
| Sample I.D.:     | See below | Client:          | STOODY CO. |
| Sample Received: | 03/29/89  | Client Ref. No.: | 21171.00   |
| Sample Analyzed: | 04/12/89  | Lab Client Code: | 0471       |
| Sample Matrix:   | Water     | Lab No.:         | 8903183    |

[illegible]

Limit of detection: 1

Method Reference: EPA 180.1

< = less than, below limit of detection

# ENVIRONMENTAL CONSULTANTS

**A Marsh & McLennan Company**

**DISTRIBUTION:**

|        |   |                    |
|--------|---|--------------------|
| WHITE  | - | Clayton Laboratory |
| YELLOW | - | Clayton Accounting |
| PINK   | - | Client Retains     |

February 3, 1989

CLAYTON ENVIRONMENTAL CONSULTANTS  
5736 Corporate Avenue  
Cypress, CA 90630

Attn: Ken Vernon

JOB NO. 11828

RECEIVED

FEB 7 1989

**WCAS**

**WEST COAST  
ANALYTICAL  
SERVICE, INC.**

ANALYTICAL CHEMISTS

A

---

LABORATORY REPORT

---


Samples Received: Five (5) soil samples  
Date Received: 1-24-89  
Purchase Order No: 2051/Proj#: 21171.00


The samples were analyzed as follows:

| <u>Samples Analyzed</u> | <u>Analysis</u>                              | <u>Results</u> |
|-------------------------|--|----------------|
| Five (5) soils          | Volatile Organics<br>by EPA 8240             | Data Sheets    |
| Five (5) soils          | Total Petroleum Hydrocarbons<br>by EPA 418.1 | Table I        |

Page 1 of 2

---

  
Michael Shelton  
Senior Chemist

  
D.J. Northington, Ph.D.  
Technical Director

---

WEST COAST ANALYTICAL SERVICE, INC.

CLAYTON ENVIRONMENTAL CONSULTANTS  
Mr. Ken Vernon

Job # 11828  
February 3, 1989

---

LABORATORY REPORT

---

TABLE I

Parts Per Million (ug/g)

| <u>Sample No.</u> | <u>Total Petroleum Hydrocarbons</u> |
|-------------------|-------------------------------------|
| Stoody SB-5,25'   | ND                                  |
| Stoody SB-6,1'    | ND                                  |
| Stoody SB-6,25'   | ND                                  |
| Stoody SB-7,1'    | ND                                  |
| Stoody SB-7,25'   | ND                                  |
| Detection Limit   | 10                                  |

ND-Not Detected

Date Analyzed: 1-26-89



CLIENT: CLAYTON ENVIRONMENTAL  
WCAS JOB #: 11828

SAMPLE: Stooddy SB-5,25'

DATE RECEIVED: 01/24/89  
DATE EXTRACTED: 02/01/89  
DATE ANALYZED: 02/01/89

RUN NUMBER: 11828V1  
SAMPLE AMOUNT: 1.0G  
MATRIX: SOIL

EPA METHOD 8240 (624)

UNITS: UG/KG (PPB)

| CAS #      | COMPOUND                    | CONCENTRATION | DET LIMIT |
|------------|-----------------------------|---------------|-----------|
| 67-64-1    | ACETONE                     | ND            | 50.       |
| 71-43-2    | BENZENE                     | ND            | 5.        |
| 75-27-4    | BROMODICHLOROMETHANE        | ND            | 5.        |
| 75-25-2    | BROMOFORM                   | ND            | 5.        |
| 74-83-9    | BROMOMETHANE                | ND            | 30.       |
| 78-93-3    | 2-BUTANONE (MEK)            | ND            | 50.       |
| 75-15-0    | CARBON DISULFIDE            | ND            | 5.        |
| 56-23-5    | CARBON TETRACHLORIDE        | ND            | 5.        |
| 108-90-7   | CHLOROBENZENE               | ND            | 5.        |
| 75-00-3    | CHLOROETHANE                | ND            | 30.       |
| 110-75-8   | 2-CHLOROETHYL VINYL ETHER   | ND            | 50.       |
| 67-66-3    | CHLOROFORM                  | ND            | 5.        |
| 74-87-3    | CHLOROMETHANE               | ND            | 30.       |
| 108-41-8   | CHLOROTOLUENE               | ND            | 5.        |
| 124-48-1   | DIBROMOCHLOROMETHANE        | ND            | 5.        |
| 95-50-1    | 1,2-DICHLOROBENZENE         | ND            | 5.        |
| 541-73-1   | 1,3-DICHLOROBENZENE         | ND            | 5.        |
| 106-46-7   | 1,4-DICHLOROBENZENE         | ND            | 5.        |
| 75-34-3    | 1,1-DICHLOROETHANE          | ND            | 5.        |
| 107-06-2   | 1,2-DICHLOROETHANE          | ND            | 5.        |
| 75-35-4    | 1,1-DICHLOROETHYLENE        | ND            | 5.        |
| 156-59-4   | CIS-1,2-DICHLOROETHYLENE    | ND            | 5.        |
| 156-60-5   | TRANS-1,2-DICHLOROETHYLENE  | ND            | 5.        |
| 78-87-5    | 1,2-DICHLOROPROPANE         | ND            | 5.        |
| 10061-01-5 | CIS-1,3-DICHLOROPROPENE     | ND            | 5.        |
| 10061-02-6 | TRANS-1,3-DICHLOROPROPENE   | ND            | 5.        |
| 100-41-4   | ETHYLBENZENE                | ND            | 5.        |
| 106-93-4   | ETHYLENE DIBROMIDE          | ND            | 5.        |
| 76-13-1    | FREON-TF                    | ND            | 5.        |
| 119-78-6   | 2-HEXANONE                  | ND            | 30.       |
| 75-09-2    | METHYLENE CHLORIDE          | ND            | 50.       |
| 108-10-1   | 4-METHYL-2-PENTANONE (MIBK) | ND            | 30.       |
| 100-42-5   | STYRENE                     | ND            | 5.        |
| 79-34-5    | 1,1,2,2-TETRACHLOROETHANE   | ND            | 5.        |
| 127-18-4   | TETRACHLOROETHYLENE         | ND            | 5.        |
| 109-99-9   | TETRAHYDROFURAN             | ND            | 5.        |
| 108-88-3   | TOLUENE                     | ND            | 5.        |
| 71-55-6    | 1,1,1-TRICHLOROETHANE       | ND            | 5.        |
| 79-00-5    | 1,1,2-TRICHLOROETHANE       | ND            | 5.        |
| 79-01-6    | TRICHLOROETHYLENE           | ND            | 5.        |
| 75-69-4    | TRICHLOROFLUOROMETHANE      | ND            | 5.        |
| 108-05-4   | VINYL ACETATE               | ND            | 30.       |
| 75-01-4    | VINYL CHLORIDE              | ND            | 30.       |
| 95-47-6    | TOTAL XYLENES               | ND            | 5.        |

TENTATIVELY IDENTIFIED COMPOUNDS

CLIENT: CLAYTON ENVIRONMENTAL  
WCAS JOB #: 11828

SAMPLE: Stooddy SB-5,25'

UNITS: UG/KG (PPB)  
APPROXIMATE

COMPOUND NAME

FRACTION CONCENTRATION

1 NONE FOUND

VOA

WCAS

CLIENT: CLAYTON ENVIRONMENTAL  
WCAS JOB #: 11828

SAMPLE: Stooddy SB-6,1'

DATE RECEIVED: 01/24/89  
DATE EXTRACTED: 02/01/89  
DATE ANALYZED: 02/01/89

RUN NUMBER: 11828V3  
SAMPLE AMOUNT: 1.0G  
MATRIX: SOIL

EPA METHOD 8240 (624)

UNITS: UG/KG (PPB)

| CAS #      | COMPOUND                    | CONCENTRATION | DET LIMIT |
|------------|-----------------------------|---------------|-----------|
| 67-64-1    | ACETONE                     | ND            | 50.       |
| 71-43-2    | BENZENE                     | ND            | 5.        |
| 75-27-4    | BROMODICHLOROMETHANE        | ND            | 5.        |
| 75-25-2    | BROMOFORM                   | ND            | 5.        |
| 74-83-9    | BROMOMETHANE                | ND            | 30.       |
| 78-93-3    | 2-BUTANONE (MEK)            | ND            | 50.       |
| 75-15-0    | CARBON DISULFIDE            | ND            | 5.        |
| 56-23-5    | CARBON TETRACHLORIDE        | ND            | 5.        |
| 108-90-7   | CHLOROBENZENE               | ND            | 5.        |
| 75-00-3    | CHLOROETHANE                | ND            | 30.       |
| 110-75-8   | 2-CHLOROETHYLVINYL ETHER    | ND            | 50.       |
| 67-66-3    | CHLOROFORM                  | ND            | 5.        |
| 74-87-3    | CHLOROMETHANE               | ND            | 30.       |
| 108-41-8   | CHLOROTOLUENE               | ND            | 5.        |
| 124-48-1   | DIBROMOCHLOROMETHANE        | ND            | 5.        |
| 95-50-1    | 1,2-DICHLOROBENZENE         | ND            | 5.        |
| 541-73-1   | 1,3-DICHLOROBENZENE         | ND            | 5.        |
| 106-46-7   | 1,4-DICHLOROBENZENE         | ND            | 5.        |
| 75-34-3    | 1,1-DICHLOROETHANE          | ND            | 5.        |
| 107-06-2   | 1,2-DICHLOROETHANE          | ND            | 5.        |
| 75-35-4    | 1,1-DICHLOROETHYLENE        | ND            | 5.        |
| 156-59-4   | CIS-1,2-DICHLOROETHYLENE    | ND            | 5.        |
| 156-60-5   | TRANS-1,2-DICHLOROETHYLENE  | ND            | 5.        |
| 78-87-5    | 1,2-DICHLOROPROPANE         | ND            | 5.        |
| 10061-01-5 | CIS-1,3-DICHLOROPROPENE     | ND            | 5.        |
| 10061-02-6 | TRANS-1,3-DICHLOROPROPENE   | ND            | 5.        |
| 100-41-4   | ETHYLBENZENE                | ND            | 5.        |
| 106-93-4   | ETHYLENE DIBROMIDE          | ND            | 5.        |
| 76-13-1    | FREON-TF                    | ND            | 5.        |
| 119-78-6   | 2-HEXANONE                  | ND            | 30.       |
| 75-09-2    | METHYLENE CHLORIDE          | ND            | 50.       |
| 108-10-1   | 4-METHYL-2-PENTANONE (MIBK) | ND            | 30.       |
| 100-42-5   | STYRENE                     | ND            | 5.        |
| 79-34-5    | 1,1,2,2-TETRACHLOROETHANE   | ND            | 5.        |
| 127-18-4   | TETRACHLOROETHYLENE         | ND            | 5.        |
| 109-99-9   | TETRAHYDROFURAN             | ND            | 5.        |
| 108-88-3   | TOLUENE                     | ND            | 5.        |
| 71-55-6    | 1,1,1-TRICHLOROETHANE       | ND            | 5.        |
| 79-00-5    | 1,1,2-TRICHLOROETHANE       | ND            | 5.        |
| 79-01-6    | TRICHLOROETHYLENE           | ND            | 5.        |
| 75-69-4    | TRICHLOROFLUOROMETHANE      | ND            | 5.        |
| 108-05-4   | VINYL ACETATE               | ND            | 30.       |
| 75-01-4    | VINYL CHLORIDE              | ND            | 30.       |
| 95-47-6    | TOTAL XYLENES               | ND            | 5.        |

TENTATIVELY IDENTIFIED COMPOUNDS

CLIENT: CLAYTON ENVIRONMENTAL  
WCAS JOB #: 11828

SAMPLE: Stooddy SB-6,1'

UNITS: UG/KG (PPB)

APPROXIMATE

COMPOUND NAME

FRACTION CONCENTRATION

1 NONE FOUND

VOA

WCAS

CLIENT: CLAYTON ENVIRONMENTAL  
WCAS JOB #: 11828

SAMPLE: Stooddy SB-6,25'

DATE RECEIVED: 01/24/89  
DATE EXTRACTED: 02/01/89  
DATE ANALYZED: 02/01/89

RUN NUMBER: 11828V4  
SAMPLE AMOUNT: 1.0G  
MATRIX: SOIL

EPA METHOD 8240 (624)

UNITS: UG/KG (PPB)

| CAS #      | COMPOUND                    | CONCENTRATION | DET LIMIT |
|------------|-----------------------------|---------------|-----------|
| 67-64-1    | ACETONE                     | ND            | 50.       |
| 71-43-2    | BENZENE                     | ND            | 5.        |
| 75-27-4    | BROMODICHLOROMETHANE        | ND            | 5.        |
| 75-25-2    | BROMOFORM                   | ND            | 5.        |
| 74-83-9    | BROMOMETHANE                | ND            | 30.       |
| 78-93-3    | 2-BUTANONE (MEK)            | ND            | 50.       |
| 75-15-0    | CARBON DISULFIDE            | 7.            | 5.        |
| 56-23-5    | CARBON TETRACHLORIDE        | ND            | 5.        |
| 108-90-7   | CHLOROBENZENE               | ND            | 5.        |
| 75-00-3    | CHLOROETHANE                | ND            | 30.       |
| 110-75-8   | 2-CHLOROETHYL VINYL ETHER   | ND            | 50.       |
| 67-66-3    | CHLOROFORM                  | ND            | 5.        |
| 74-87-3    | CHLOROMETHANE               | ND            | 30.       |
| 108-41-8   | CHLOROTOLUENE               | ND            | 5.        |
| 124-48-1   | DIBROMOCHLOROMETHANE        | ND            | 5.        |
| 95-50-1    | 1,2-DICHLOROBENZENE         | ND            | 5.        |
| 541-73-1   | 1,3-DICHLOROBENZENE         | ND            | 5.        |
| 106-46-7   | 1,4-DICHLOROBENZENE         | ND            | 5.        |
| 75-34-3    | 1,1-DICHLOROETHANE          | ND            | 5.        |
| 107-06-2   | 1,2-DICHLOROETHANE          | ND            | 5.        |
| 75-35-4    | 1,1-DICHLOROETHYLENE        | ND            | 5.        |
| 156-59-4   | CIS-1,2-DICHLOROETHYLENE    | ND            | 5.        |
| 156-60-5   | TRANS-1,2-DICHLOROETHYLENE  | ND            | 5.        |
| 78-87-5    | 1,2-DICHLOROPROPANE         | ND            | 5.        |
| 10061-01-5 | CIS-1,3-DICHLOROPROPENE     | ND            | 5.        |
| 10061-02-6 | TRANS-1,3-DICHLOROPROPENE   | ND            | 5.        |
| 100-41-4   | ETHYLBENZENE                | ND            | 5.        |
| 106-93-4   | ETHYLENE DIBROMIDE          | ND            | 5.        |
| 76-13-1    | FREON-TF                    | ND            | 5.        |
| 119-78-6   | 2-HEXANONE                  | ND            | 30.       |
| 75-09-2    | METHYLENE CHLORIDE          | ND            | 50.       |
| 108-10-1   | 4-METHYL-2-PENTANONE (MIBK) | ND            | 30.       |
| 100-42-5   | STYRENE                     | ND            | 5.        |
| 79-34-5    | 1,1,2,2-TETRACHLOROETHANE   | ND            | 5.        |
| 127-18-4   | TETRACHLOROETHYLENE         | ND            | 5.        |
| 109-99-9   | TETRAHYDROFURAN             | ND            | 5.        |
| 108-88-3   | TOLUENE                     | ND            | 5.        |
| 71-55-6    | 1,1,1-TRICHLOROETHANE       | ND            | 5.        |
| 79-00-5    | 1,1,2-TRICHLOROETHANE       | ND            | 5.        |
| 79-01-6    | TRICHLOROETHYLENE           | ND            | 5.        |
| 75-69-4    | TRICHLOROFLUOROMETHANE      | ND            | 5.        |
| 108-05-4   | VINYL ACETATE               | ND            | 30.       |
| 75-01-4    | VINYL CHLORIDE              | ND            | 30.       |
| 95-47-6    | TOTAL XYLENES               | ND            | 5.        |

TENTATIVELY IDENTIFIED COMPOUNDS

CLIENT: CLAYTON ENVIRONMENTAL  
WCAS JOB #: 11828

SAMPLE: Stooddy SB-6,25'

UNITS: UG/KG (PPB)  
APPROXIMATE

COMPOUND NAME

FRACTION CONCENTRATION

1 NONE FOUND

VOA

WCAS

CLIENT: CLAYTON ENVIRONMENTAL  
WCAS JOB #: 11828

SAMPLE: Stooddy SB-7,1'

DATE RECEIVED: 01/24/89  
DATE EXTRACTED: 02/01/89  
DATE ANALYZED: 02/01/89

RUN NUMBER: 11828V5  
SAMPLE AMOUNT: 1.0G  
MATRIX: SOIL

EPA METHOD 8240 (624)

UNITS: UG/KG (PPB)

| CAS #      | COMPOUND                    | CONCENTRATION | DET LIMIT |
|------------|-----------------------------|---------------|-----------|
| 67-64-1    | ACETONE                     | ND            | 50.       |
| 71-43-2    | BENZENE                     | ND            | 5.        |
| 75-27-4    | BROMODICHLOROMETHANE        | ND            | 5.        |
| 75-25-2    | BROMOFORM                   | ND            | 5.        |
| 74-83-9    | BROMOMETHANE                | ND            | 30.       |
| 78-93-3    | 2-BUTANONE (MEK)            | ND            | 50.       |
| 75-15-0    | CARBON DISULFIDE            | ND            | 5.        |
| 56-23-5    | CARBON TETRACHLORIDE        | ND            | 5.        |
| 108-90-7   | CHLOROBENZENE               | ND            | 5.        |
| 75-00-3    | CHLOROETHANE                | ND            | 30.       |
| 110-75-8   | 2-CHLOROETHYL VINYL ETHER   | ND            | 50.       |
| 67-66-3    | CHLOROFORM                  | ND            | 5.        |
| 74-87-3    | CHLOROMETHANE               | ND            | 30.       |
| 108-41-8   | CHLOROTOLUENE               | ND            | 5.        |
| 124-48-1   | DIBROMOCHLOROMETHANE        | ND            | 5.        |
| 95-50-1    | 1,2-DICHLOROBENZENE         | ND            | 5.        |
| 541-73-1   | 1,3-DICHLOROBENZENE         | ND            | 5.        |
| 106-46-7   | 1,4-DICHLOROBENZENE         | ND            | 5.        |
| 75-34-3    | 1,1-DICHLOROETHANE          | ND            | 5.        |
| 107-06-2   | 1,2-DICHLOROETHANE          | ND            | 5.        |
| 75-35-4    | 1,1-DICHLOROETHYLENE        | ND            | 5.        |
| 156-59-4   | CIS-1,2-DICHLOROETHYLENE    | ND            | 5.        |
| 156-60-5   | TRANS-1,2-DICHLOROETHYLENE  | ND            | 5.        |
| 78-87-5    | 1,2-DICHLOROPROPANE         | ND            | 5.        |
| 10061-01-5 | CIS-1,3-DICHLOROPROPENE     | ND            | 5.        |
| 10061-02-6 | TRANS-1,3-DICHLOROPROPENE   | ND            | 5.        |
| 100-41-4   | ETHYLBENZENE                | ND            | 5.        |
| 106-93-4   | ETHYLENE DIBROMIDE          | ND            | 5.        |
| 76-13-1    | FREON-TF                    | ND            | 5.        |
| 119-78-6   | 2-HEXANONE                  | ND            | 30.       |
| 75-09-2    | METHYLENE CHLORIDE          | ND            | 50.       |
| 108-10-1   | 4-METHYL-2-PENTANONE (MIBK) | ND            | 30.       |
| 100-42-5   | STYRENE                     | ND            | 5.        |
| 79-34-5    | 1,1,2,2-TETRACHLOROETHANE   | ND            | 5.        |
| 127-18-4   | TETRACHLOROETHYLENE         | ND            | 5.        |
| 109-99-9   | TETRAHYDROFURAN             | ND            | 5.        |
| 108-88-3   | TOLUENE                     | ND            | 5.        |
| 71-55-6    | 1,1,1-TRICHLOROETHANE       | ND            | 5.        |
| 79-00-5    | 1,1,2-TRICHLOROETHANE       | ND            | 5.        |
| 79-01-6    | TRICHLOROETHYLENE           | ND            | 5.        |
| 75-69-4    | TRICHLOROFLUOROMETHANE      | ND            | 5.        |
| 108-05-4   | VINYL ACETATE               | ND            | 30.       |
| 75-01-4    | VINYL CHLORIDE              | ND            | 30.       |
| 95-47-6    | TOTAL XYLENES               | ND            | 5.        |

TENTATIVELY IDENTIFIED COMPOUNDS

CLIENT: CLAYTON ENVIRONMENTAL  
WCAS JOB #: 11828

SAMPLE: Stooddy SB-7,1'

UNITS: UG/KG (PPB)

APPROXIMATE

COMPOUND NAME

FRACTION CONCENTRATION

1 NONE FOUND

VOA

WCAS



CLIENT: CLAYTON ENVIRONMENTAL  
WCAS JOB #: 11828

SAMPLE: Stooddy SB-7,25'

DATE RECEIVED: 01/24/89  
DATE EXTRACTED: 02/01/89  
DATE ANALYZED: 02/01/89

RUN NUMBER: 11828V2  
SAMPLE AMOUNT: 1.0G  
MATRIX: SOIL

EPA METHOD 8240 (624)

UNITS: UG/KG (PPB)

| CAS #      | COMPOUND                    | CONCENTRATION | DET LIMIT |
|------------|-----------------------------|---------------|-----------|
| 67-64-1    | ACETONE                     | ND            | 50.       |
| 71-43-2    | BENZENE                     | ND            | 5.        |
| 75-27-4    | BROMODICHLOROMETHANE        | ND            | 5.        |
| 75-25-2    | BROMOFORM                   | ND            | 5.        |
| 74-83-9    | BROMOMETHANE                | ND            | 30.       |
| 78-93-3    | 2-BUTANONE (MEK)            | ND            | 50.       |
| 75-15-0    | CARBON DISULFIDE            | ND            | 5.        |
| 56-23-5    | CARBON TETRACHLORIDE        | ND            | 5.        |
| 108-90-7   | CHLOROBENZENE               | ND            | 5.        |
| 75-00-3    | CHLOROETHANE                | ND            | 30.       |
| 110-75-8   | 2-CHLOROETHYL VINYL ETHER   | ND            | 50.       |
| 67-66-3    | CHLOROFORM                  | ND            | 5.        |
| 74-87-3    | CHLOROMETHANE               | ND            | 30.       |
| 108-41-8   | CHLOROTOLUENE               | ND            | 5.        |
| 124-48-1   | DIBROMOCHLOROMETHANE        | ND            | 5.        |
| 95-50-1    | 1,2-DICHLOROBENZENE         | ND            | 5.        |
| 541-73-1   | 1,3-DICHLOROBENZENE         | ND            | 5.        |
| 106-46-7   | 1,4-DICHLOROBENZENE         | ND            | 5.        |
| 75-34-3    | 1,1-DICHLOROETHANE          | ND            | 5.        |
| 107-06-2   | 1,2-DICHLOROETHANE          | ND            | 5.        |
| 75-35-4    | 1,1-DICHLOROETHYLENE        | ND            | 5.        |
| 156-59-4   | CIS-1,2-DICHLOROETHYLENE    | ND            | 5.        |
| 156-60-5   | TRANS-1,2-DICHLOROETHYLENE  | ND            | 5.        |
| 78-87-5    | 1,2-DICHLOROPROPANE         | ND            | 5.        |
| 10061-01-5 | CIS-1,3-DICHLOROPROPENE     | ND            | 5.        |
| 10061-02-6 | TRANS-1,3-DICHLOROPROPENE   | ND            | 5.        |
| 100-41-4   | ETHYLBENZENE                | ND            | 5.        |
| 106-93-4   | ETHYLENE DIBROMIDE          | ND            | 5.        |
| 76-13-1    | FREON-TF                    | ND            | 5.        |
| 119-78-6   | 2-HEXANONE                  | ND            | 30.       |
| 75-09-2    | METHYLENE CHLORIDE          | ND            | 50.       |
| 108-10-1   | 4-METHYL-2-PENTANONE (MIBK) | ND            | 30.       |
| 100-42-5   | STYRENE                     | ND            | 5.        |
| 79-34-5    | 1,1,2,2-TETRACHLOROETHANE   | ND            | 5.        |
| 127-18-4   | TETRACHLOROETHYLENE         | ND            | 5.        |
| 109-99-9   | TETRAHYDROFURAN             | ND            | 5.        |
| 108-88-3   | TOLUENE                     | ND            | 5.        |
| 71-55-6    | 1,1,1-TRICHLOROETHANE       | ND            | 5.        |
| 79-00-5    | 1,1,2-TRICHLOROETHANE       | ND            | 5.        |
| 79-01-6    | TRICHLOROETHYLENE           | ND            | 5.        |
| 75-69-4    | TRICHLOROFLUOROMETHANE      | ND            | 5.        |
| 108-05-4   | VINYL ACETATE               | ND            | 30.       |
| 75-01-4    | VINYL CHLORIDE              | ND            | 30.       |
| 95-47-6    | TOTAL XYLENES               | ND            | 5.        |

TENTATIVELY IDENTIFIED COMPOUNDS

CLIENT: CLAYTON ENVIRONMENTAL  
WCAS JOB #: 11828

SAMPLE: Stooddy SB-7,25'

UNITS: UG/KG (PPB)

APPROXIMATE

COMPOUND NAME

FRACTION CONCENTRATION

1 NONE FOUND

VOA

## Data Reporting Qualifiers

- Value - If the result is a value greater than or equal to the Detection Limit (DL), the value is reported.
- ND - Indicates that the compound was analyzed for but not detected. The minimum DL for the sample with the ND is reported based on necessary concentration or dilution actions.
- TR - Indicates an estimated value. This flag is used when the mass spectral data indicates the presence of a compound that meets the identification criteria but the result is less than the specified DL but greater than zero.

# CHAIN OF CUSTODY

## CLAYTON ENVIRONMENTAL CONSULTANTS

1 of 1

**SAMPLERS:** (Signature) KEN VERNON (Ken Vernon)  
**PHONE:** (714) 229-4806  
**ANALYTICAL LABORATORY**  
WEST COAST ANALYTICAL SERVICES, INC.  
9480 ALBERTIS AVE.  
SANTA FE SPRINGS, CA. 90670  
**ATTN:** SAMPLE RECEIVING  
**PHONE:** (213) 948-2225  
**SHIPMENT SERVICE:** Fed. Ex.  
**AIRBILL #:** 9145828090

**CLIENT INFORMATION**  
**CONTACT NAME:** KEN VERNON  
**COMPANY NAME:** CLAYTON ENVIRONMENTAL  
**PHONE NO.:** (714) 229-4806  
**P.O./JOB#:** 21171.00  
**COMPANY ADDRESS:** 5736 CORPORATE AVE.  
P.O. Box 788  
CYPRESS, CA. 90630-0788  
**BILLING ADDRESS:** SAME

|   |  |                        |                       |
|---|--|------------------------|-----------------------|
| Relinquished by: (Signature)<br><u>Ken Vernon</u> | Received by: (Signature)<br><u>MSABANT. NCAS</u> | Date<br><u>1-24-89</u> | Time<br><u>1000am</u> |
| Relinquished by: (Signature)                      | Received by: (Signature)<br><u>#11828</u>        | Date                   | Time                  |

\*Analysis laboratory should complete "Sample Condition Upon Receipt", section below, sign and return top copy to Clayton Environmental Consultants, Inc., P.O. Box 9019, Pleasanton, California 94566

| CLAYTON LAB BATCH # |                        |                |             |              | LAB CLIENT CODE |       |   |             |
|---------------------|------------------------|----------------|-------------|--------------|-----------------|-------|---|-------------|
| Dash #              | Sample I.D.            | Date Sampled   | Matrix      | Quan. (Dup.) | Cont. Size      | Pres. | Analysis Requested                        | Cond. Rec'd |
| <u>1</u>            | <u>Stony, 58-5.25'</u> | <u>1-23-89</u> | <u>Soil</u> | <u>1</u>     | <u>BC</u>       |       | <u>EPA 8240 (PLS)</u><br><u>EPA 418.1</u> |             |
| <u>1</u>            | <u>Stony, 58-6.1'</u>  | <u>"</u>       | <u>"</u>    | <u>"</u>     | <u>"</u>        |       | <u>EPA 8240 (PLS)</u><br><u>EPA 418.1</u> |             |
| <u>1</u>            | <u>Stony, 58-6.25'</u> | <u>1-23-89</u> | <u>Soil</u> | <u>"</u>     | <u>"</u>        |       | <u>EPA 8240 (PLS)</u><br><u>EPA 418.1</u> |             |
| <u>1</u>            | <u>Stony, 58-7.1'</u>  | <u>1-23-89</u> | <u>"</u>    | <u>"</u>     | <u>"</u>        |       | <u>EPA 8240 (PLS)</u><br><u>EPA 418.1</u> |             |
| <u>1</u>            | <u>Stony, 58-7.25'</u> | <u>"</u>       | <u>"</u>    | <u>"</u>     | <u>"</u>        |       | <u>EPA 8240 (PLS)</u><br><u>EPA 418.1</u> |             |
|                     |                        |                |             |              |                 |       |   |             |
|                     |                        |                |             |              |                 |       |   |             |
|                     |                        |                |             |              |                 |       |   |             |
|                     |                        |                |             |              |                 |       |   |             |
|                     |                        |                |             |              |                 |       |   |             |
|                     |                        |                |             |              |                 |       |   |             |
|                     |                        |                |             |              |                 |       |   |             |
|                     |                        |                |             |              |                 |       |   |             |
|                     |                        |                |             |              |                 |       |   |             |
|                     |                        |                |             |              |                 |       |   |             |
|                     |                        |                |             |              |                 |       |   |             |

|                          |                     |                   |                |
|--------------------------|---------------------|-------------------|----------------|
| BC-BRASS CORE            | FIL-FILTER          | WM-WIDE MOUTH     | CONDITIONS     |
| SSC-STAINLESS STEEL CORE | CAS-CASSETTE        | OVN-ORGANIC VAPOR |                |
| CUT-COPPER TUBE          | CHT-CHARCOAL TUBE   | MONITOR           |                |
| SQ-WIDE MOUTH SQUAT JAR  | SGT-SILICA GEL TUBE |                   | HDSP-HEADSPACE |
|                          |                     |                   | A/B-AIR BUBBLE |

# Clayton Environmental Consultants, Inc.

P.O. Box 9019 • 1252 Quarry Lane • Pleasanton, CA 94566 • (415) 426-2600

February 8, 1989

Mr. Ken Vernon  
CLAYTON ENVIRONMENTAL CONSULTANTS, INC.  
5736 Corporate Avenue  
P.O. Box 788  
Cypress, CA 90630-0788

Client Ref. No.: 21171.00  
Lab Batch No.: 8902022  
Clayton Project No.: 21171.77  
Client Code No.: 0471


Dear Mr. Vernon:

Attached is our analytical laboratory report for the samples received on February 3, 1989. A copy of the Chain of Custody form acknowledging receipt of these samples is attached.

Please note that any unused portion of the samples will be retained at our facility for approximately 30 days after the date of this report, unless you have requested otherwise.

We appreciate the opportunity to be of assistance to you. If you have any questions, please contact Client Services at (415) 426-2657.

Sincerely,

  
Ronald H. Peters, CIH  
Manager, Laboratory Services

RHP/mn  
Attachment

## INORGANIC LABORATORY ANALYSES

|                  |           |                  |          |
|------------------|-----------|------------------|----------|
| Sample I.D.:     | See below | Client:          | Stoody   |
| Sample Received: | 02/03/89  | Client Ref. No.: | 21171.00 |
| Sample Analyzed: | 02/03/89  | Lab Client Code: | 0471     |
| Sample Matrix:   | Water     | Lab No.:         | 8902022  |

[illegible]

Limit of detection: 0.1

Method Reference: EPA 180.1

\* = Nephelometric Turbidity Units

**EPA METHOD 624  
PURGEABLE ORGANICS**

|                  |          |                  |            |
|------------------|----------|------------------|------------|
| Sample I.D.:     | MW -1A   | Client:          | Stoody     |
| Sample Received: | 02/03/89 | Client Ref. No.: | 21171.00   |
| Sample Analyzed: | 02/03/89 | Lab Client Code: | 0471       |
| Sample Matrix:   | Water    | Lab No.:         | 8902022-01 |

| <u>Compound</u>           | <u>Concentration<br/>µg/L (ppb)</u> | <u>Limit of Detection<br/>µg/L (ppb)</u> |
|---------------------------|-------------------------------------|--|
| Chloromethane             | ND                                  | 10                                       |
| Bromomethane              | ND                                  | 4  |
| Vinyl chloride            | ND                                  | 4  |
| Chloroethane              | ND                                  | 4  |
| Methylene chloride        | ND                                  | 10                                       |
| Trichlorofluoromethane    | ND                                  | 3  |
| 1,1-dichloroethene        | 31                                  | 3  |
| 1,1-dichloroethane        | ND                                  | 3  |
| Trans-1,2-dichloroethene  | ND                                  | 3  |
| Chloroform                | ND                                  | 3  |
| 1,2-dichloroethane        | ND                                  | 3  |
| 1,1,1-trichloroethane     | ND                                  | 3  |
| Carbon tetrachloride      | ND                                  | 3  |
| Bromodichloromethane      | ND                                  | 3  |
| 1,2-dichloropropane       | ND                                  | 3  |
| Cis-1,3-dichloropropene   | ND                                  | 3  |
| Trichloroethene           | 130                                 | 4  |
| Benzene                   | ND                                  | 2  |
| Dibromochloromethane      | ND                                  | 2  |
| 1,1,2-trichloroethane     | ND                                  | 6  |
| Trans-1,3-dichloropropene | ND                                  | 5  |
| 2-chloroethylvinylether   | ND                                  | 3  |
| Bromoform                 | ND                                  | 3  |
| 1,1,2,2-tetrachloroethane | ND                                  | 4  |
| Tetrachloroethene         | 190                                 | 4  |
| Toluene                   | 3                                   | 2  |
| Chlorobenzene             | ND                                  | 3  |
| Ethylbenzene              | ND                                  | 3  |
| 1,3-dichlorobenzene       | ND                                  | 3  |
| 1,2-dichlorobenzene       | ND                                  | 3  |
| 1,4-dichlorobenzene       | ND                                  | 3  |
| Freon 113                 | 10                                  | 3  |
| Total Xylenes             | ND                                  | 3  |

ND = Not detected at or above limit of detection.

**PURGEABLE ORGANICS**  
**TENTATIVE IDENTIFICATION OF NON-PRIORITY POLLUTANTS**

|                  |          |                  |            |
|------------------|----------|------------------|------------|
| Sample I.D.:     | MW-1A    | Client:          | STOODY     |
| Sample Received: | 02/03/89 | Client Ref. No.: | 21171.00   |
| Sample Analyzed: | 02/03/89 | Lab Client Code: | 0471       |
| Sample Matrix:   | Water    | Lab No.:         | 8902022-01 |

[illegible]

ND = Not detected at or above limit of detection

Tentative Identification based on nearest match to NBS library.

\* Estimated concentration based on peak area response of nearest internal standard.



EPA METHOD 624  
PURGEABLE ORGANICS

|                  |          |                  |            |
|------------------|----------|------------------|------------|
| Sample I.D.:     | MW -2A   | Client:          | Stoody     |
| Sample Received: | 02/03/89 | Client Ref. No.: | 21171.00   |
| Sample Analyzed: | 02/03/89 | Lab Client Code: | 0471       |
| Sample Matrix:   | Water    | Lab No.:         | 8902022-02 |

| Compound                  | Concentration<br><u>µg/L (ppb)</u> | Limit of Detection<br><u>µg/L (ppb)</u> |
|---------------------------|------------------------------------|---|
| Chloromethane             | ND                                 | 10                                      |
| Bromomethane              | ND                                 | 4                                       |
| Vinyl chloride            | ND                                 | 4                                       |
| Chloroethane              | ND                                 | 4                                       |
| Methylene chloride        | ND                                 | 10                                      |
| Trichlorofluoromethane    | ND                                 | 3                                       |
| 1,1-dichloroethene        | 61                                 | 3                                       |
| 1,1-dichloroethane        | ND                                 | 3                                       |
| Trans-1,2-dichloroethene  | ND                                 | 3                                       |
| Chloroform                | ND                                 | 3                                       |
| 1,2-dichloroethane        | ND                                 | 3                                       |
| 1,1,1-trichloroethane     | ND                                 | 3                                       |
| Carbon tetrachloride      | ND                                 | 3                                       |
| Bromodichloromethane      | ND                                 | 3                                       |
| 1,2-dichloropropane       | ND                                 | 3                                       |
| Cis-1,3-dichloropropene   | ND                                 | 3                                       |
| Trichloroethene           | 130                                | 4                                       |
| Benzene                   | 31                                 | 2                                       |
| Dibromochloromethane      | ND                                 | 2                                       |
| 1,1,2-trichloroethane     | ND                                 | 6                                       |
| Trans-1,3-dichloropropene | ND                                 | 5                                       |
| 2-chloroethylvinylether   | ND                                 | 3                                       |
| Bromoform                 | ND                                 | 3                                       |
| 1,1,2,2-tetrachloroethane | ND                                 | 4                                       |
| Tetrachloroethene         | 160                                | 4                                       |
| Toluene                   | 39                                 | 2                                       |
| Chlorobenzene             | 39                                 | 3                                       |
| Ethylbenzene              | ND                                 | 3                                       |
| 1,3-dichlorobenzene       | ND                                 | 3                                       |
| 1,2-dichlorobenzene       | ND                                 | 3                                       |
| 1,4-dichlorobenzene       | ND                                 | 3                                       |
| Freon 113                 | 8                                  | 3                                       |
| Total Xylenes             | ND                                 | 3                                       |

ND = Not detected at or above limit of detection.

## EPA METHOD 624

PURGEABLE ORGANICS  
TENTATIVE IDENTIFICATION OF NON-PRIORITY POLLUTANTS

|                  |          |                  |            |
|------------------|----------|------------------|------------|
| Sample I.D.:     | MW-2A    | Client:          | STOODY     |
| Sample Received: | 02/03/89 | Client Ref. No.: | 21171.00   |
| Sample Analyzed: | 02/03/89 | Lab Client Code: | 0471       |
| Sample Matrix:   | Water    | Lab No.:         | 8902022-02 |

| <u>Scan<br/>Number</u> | <u>Compound</u> | <u>Estimated*<br/>Concentration<br/>µg/L (ppb)</u> | <u>Limit of<br/>Detection<br/>(ppb)</u> |
|------------------------|-----------------|--|---|
|------------------------|-----------------|--|---|

No additional compounds detected

ND = Not detected at or above limit of detection

Tentative Identification based on nearest match to NBS library.

\* Estimated concentration based on peak area response of nearest internal standard.

EPA METHOD 624  
PURGEABLE ORGANICS

|                  |          |                  |            |
|------------------|----------|------------------|------------|
| Sample I.D.:     | MW -3A   | Client:          | Stoody     |
| Sample Received: | 02/03/89 | Client Ref. No.: | 21171.00   |
| Sample Analyzed: | 02/03/89 | Lab Client Code: | 0471       |
| Sample Matrix:   | Water    | Lab No.:         | 8902022-03 |

| <u>Compound</u>           | <u>Concentration<br/>µg/L (ppb)</u> | <u>Limit of Detection<br/>µg/L (ppb)</u> |
|---------------------------|-------------------------------------|--|
| Chloromethane             | ND                                  | 10                                       |
| Bromomethane              | ND                                  | 4  |
| Vinyl chloride            | ND                                  | 4  |
| Chloroethane              | ND                                  | 4  |
| Methylene chloride        | ND                                  | 10                                       |
| Trichlorofluoromethane    | ND                                  | 3  |
| 1,1-dichloroethene        | ND                                  | 3  |
| 1,1-dichloroethane        | ND                                  | 3  |
| Trans-1,2-dichloroethene  | ND                                  | 3  |
| Chloroform                | ND                                  | 3  |
| 1,2-dichloroethane        | ND                                  | 3  |
| 1,1,1-trichloroethane     | ND                                  | 3  |
| Carbon tetrachloride      | ND                                  | 3  |
| Bromodichloromethane      | ND                                  | 3  |
| 1,2-dichloropropane       | ND                                  | 3  |
| Cis-1,3-dichloropropene   | ND                                  | 3  |
| Trichloroethene           | 25                                  | 4  |
| Benzene                   | ND                                  | 2  |
| Dibromochloromethane      | ND                                  | 2  |
| 1,1,2-trichloroethane     | ND                                  | 6  |
| Trans-1,3-dichloropropene | ND                                  | 5  |
| 2-chloroethylvinylether   | ND                                  | 3  |
| Bromoform                 | ND                                  | 3  |
| 1,1,2,2-tetrachloroethane | ND                                  | 4  |
| Tetrachloroethene         | 64                                  | 4  |
| Toluene                   | ND                                  | 2  |
| Chlorobenzene             | ND                                  | 3  |
| Ethylbenzene              | ND                                  | 3  |
| 1,3-dichlorobenzene       | ND                                  | 3  |
| 1,2-dichlorobenzene       | ND                                  | 3  |
| 1,4-dichlorobenzene       | ND                                  | 3  |
| Freon 113                 | ND                                  | 3  |
| Total Xylenes             | ND                                  | 3  |

ND = Not detected at or above limit of detection.

## EPA METHOD 624

PURGEABLE ORGANICS  
TENTATIVE IDENTIFICATION OF NON-PRIORITY POLLUTANTS

|                  |          |                  |            |
|------------------|----------|------------------|------------|
| Sample I.D.:     | MW-3A    | Client:          | STOODY     |
| Sample Received: | 02/03/89 | Client Ref. No.: | 21171.00   |
| Sample Analyzed: | 02/03/89 | Lab Client Code: | 0471       |
| Sample Matrix:   | Water    | Lab No.:         | 8902022-03 |

| <u>Scan<br/>Number</u> | <u>Compound</u> | <u>Estimated*<br/>Concentration<br/>µg/L (ppb)</u> | <u>Limit of<br/>Detection<br/>(ppb)</u> |
|------------------------|-----------------|--|---|
|------------------------|-----------------|--|---|

No additional compounds detected

ND = Not detected at or above limit of detection

Tentative Identification based on nearest match to NBS library.

\* Estimated concentration based on peak area response of nearest internal standard.

EPA METHOD 624  
PURGEABLE ORGANICS

|                  |              |                  |            |
|------------------|--------------|------------------|------------|
| Sample I.D.:     | Method Blank | Client:          | Stoody     |
| Sample Received: |              | Client Ref. No.: | 21171.00   |
| Sample Analyzed: | 02/03/89     | Lab Client Code: | 0471       |
| Sample Matrix:   | Water        | Lab No.:         | 8902022-MB |

| <u>Compound</u>           | <u>Concentration<br/>µg/L (ppb)</u> | <u>Limit of Detection<br/>µg/L (ppb)</u> |
|---------------------------|-------------------------------------|--|
| Chloromethane             | ND                                  | 10                                       |
| Bromomethane              | ND                                  | 4  |
| Vinyl chloride            | ND                                  | 4  |
| Chloroethane              | ND                                  | 4  |
| Methylene chloride        | ND                                  | 10                                       |
| Trichlorofluoromethane    | ND                                  | 3  |
| 1,1-dichloroethene        | ND                                  | 3  |
| 1,1-dichloroethane        | ND                                  | 3  |
| Trans-1,2-dichloroethene  | ND                                  | 3  |
| Chloroform                | ND                                  | 3  |
| 1,2-dichloroethane        | ND                                  | 3  |
| 1,1,1-trichloroethane     | ND                                  | 3  |
| Carbon tetrachloride      | ND                                  | 3  |
| Bromodichloromethane      | ND                                  | 3  |
| 1,2-dichloropropane       | ND                                  | 3  |
| Cis-1,3-dichloropropene   | ND                                  | 3  |
| Trichloroethene           | ND                                  | 4  |
| Benzene                   | ND                                  | 2  |
| Dibromochloromethane      | ND                                  | 2  |
| 1,1,2-trichloroethane     | ND                                  | 6  |
| Trans-1,3-dichloropropene | ND                                  | 5  |
| 2-chloroethylvinylether   | ND                                  | 3  |
| Bromoform                 | ND                                  | 3  |
| 1,1,2,2-tetrachloroethane | ND                                  | 4  |
| Tetrachloroethene         | ND                                  | 4  |
| Toluene                   | ND                                  | 2  |
| Chlorobenzene             | ND                                  | 3  |
| Ethylbenzene              | ND                                  | 3  |
| 1,3-dichlorobenzene       | ND                                  | 3  |
| 1,2-dichlorobenzene       | ND                                  | 3  |
| 1,4-dichlorobenzene       | ND                                  | 3  |
| Freon 113                 | ND                                  | 3  |
| Total Xylenes             | ND                                  | 3  |

ND = Not detected at or above limit of detection.

# Clayton

ENVIRONMENTAL  
CONSULTANTS

A Marsh & McLennan Company

## REQUEST FOR LABORATORY ANALYTICAL SERVICES

For Clayton Use Only Page 1 of 1

Project No. 21171.00

Batch No. 5902022

Client No. 0479

Date Received 2-3-89 By TS

Date Logged In 2-3-89 By TS

|                                |  |                                |  |   |  |   |  |
|--------------------------------|--|--------------------------------|--|---|--|---|--|
| Purchase Order No.             |  | Client Job No. <u>21171.00</u> |  | Name <u>Ken Vernon</u>  |  | Dept.   |  |
| SEND INVOICE TO                |  | Company <u>K&amp;E-CYPRESS</u> |  | Address   |  | City, State, Zip  |  |
| Date Results Required:         |  | Rush Charges Authorized?       |  | <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No |  | Special Instructions: (method, limit of detection, phone results, rush results, etc.) |  |
| * Explanation of Preservative: |  | <u>Results to Ken Vernon</u>   |  |   |  |   |  |

| CHAIN OF CUSTODY (If required) | Relinquished by:  | Date/Time     | Relinquished by: | Date/Time    | Number of Containers | REPORT RESULTS TO |                        | ANALYSIS REQUESTED<br>(Enter an 'X' in the box below to indicate request; Enter a 'P' if Preservative added) | FOR LAB USE ONLY |                |
|--------------------------------|-------------------|---------------|------------------|--------------|----------------------|-------------------|------------------------|--|------------------|----------------|
|                                |                   |               |                  |              |                      | Name              | Company                |  | City, State, Zip | Telephone No.  |
| STOBY - MW-1 (A+B)             | <u>Ken Vernon</u> | <u>2-2-89</u> | <u>Water</u>     | <u>11:45</u> | 1                    | <u>Ken Vernon</u> | <u>K&amp;E-CYPRESS</u> | <u>21171.00</u>  | <u>0479</u>      | <u>5902022</u> |
| STOBY - MW-2 (A+B)             | <u>Ken Vernon</u> | <u>"</u>      | <u>"</u>         | <u>"</u>     | 1                    | <u>Ken Vernon</u> | <u>K&amp;E-CYPRESS</u> | <u>21171.00</u>  | <u>0479</u>      | <u>5902022</u> |
| STOBY - MW-3 (A+B)             | <u>Ken Vernon</u> | <u>"</u>      | <u>"</u>         | <u>"</u>     | 1                    | <u>Ken Vernon</u> | <u>K&amp;E-CYPRESS</u> | <u>21171.00</u>  | <u>0479</u>      | <u>5902022</u> |

Authorized by: Ken Vernon Date 2-1-89

(Client Signature Must Accompany Request)

Please return completed form and samples to one of the Clayton Environmental Consultants, Inc. labs listed below:

|   |   |   |  |
|---|---|---|--|
| 22345 Roethel Drive<br>Novi, MI 48050<br>(313) 344-1770 | Raritan Center<br>160 Fieldcrest Ave.<br>Edison, NJ 08837<br>(201) 225-6040 | 400 Chaastain Center Blvd., N.W.<br>Suite 490<br>Kennesaw, GA 30144<br>(404) 499-7500 | 1252 Quarry Lane<br>Pleasanton, CA 94566<br>(415) 426-2600 |
|---|---|---|--|

DISTRIBUTION:

WHITE - Clayton Laboratory

YELLOW - Clayton Accounting

PINK - Client Retains